

SINGLE PHASE ASSEMBLIES

1. 2. 3. 4. 5. 6. 7. 8. 9. 10. 11. 12. 13. 14. 15. 16. 17. 18. 19. 20. 21. 22. 23. 24. 25. 26. 27. 28. 29. 30. 31. 32. 33. 34. 35. 36. 37. 38. 39. 40. 41. 42. 43. 44. 45. 46. 47. 48. 49. 50. 51. 52. 53. 54. 55. 56. 57. 58. 59. 60. 61. 62. 63. 64. 65. 66. 67. 68. 69. 70. 71. 72. 73. 74. 75. 76. 77. 78. 79. 80. 81. 82. 83. 84. 85. 86. 87. 88. 89. 90. 91. 92. 93. 94. 95. 96. 97. 98. 99. 100.

1111111111

1111111111
1111111111

1111111111


1111111111

1111111111

1111111111

NOTES:

1. MAXIMUM LINE ANGLE IS 10° FOR 397 ACSR & 750 AAC.
2. MAXIMUM LINE ANGLE IS 20° FOR 1/0 ACSR & 1/0 AAC.
3. IF NO FORMED WIRE TIE FOR ALUMINUM CONDUCTOR IS AVAILABLE USE LINE GUARD AND TIE WIRE.
4. COPPER CONDUCTOR—NO FORMED WIRE TIE IS AVAILABLE. DO NOT USE ALUMINUM FORMED WIRE TIES ON COPPER CONDUCTORS, USE COPPER TIE WIRE.



DETAIL POLE TOP PIN
CONDUCTOR TIE


POWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

DATE: MARCH, 1991


REVISIONS

ELECTRIC CITIES
OF GEORGIA

11.07



TOP VIEW



MAX. SPAN - 500'
0° - 6°

STANDARD CONFIGURATION STRAIGHT LINE CONSTRUCTION

A1

POWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

REVISIONS _____



ELECTRIC CITIES
OF GEORGIA

DATE: MARCH, 1991

1.01

A1

[illegible]



6°-24°

STANDARD CONFIGURATION MEDIUM LINE ANGLE CONSTRUCTION

A1PA


VER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

REVISIONS _____



ELECTRIC CITIES
OF GEORGIA

DATE: MARCH, 1991

1.02



TOP VIEW



PLAN

MAX. SPAN - 500'
0° - 6°

STANDARD CONFIGURATION SINGLE PHASE, DOUBLE PRIMARY SUPPORTS

A2

JWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

REVISIONS _____

ELECTRIC CITIES
OF GEORGIA

1.03

DATE: MARCH, 1991

CONSTRUCTION ASSEMBLY SPECIFICATIONS FOR


ELECTRIC CITIES

STANDARD CONFIGURATION

SINGLE PHASE, DOUBLE PRIMARY SUPPORTS

A2

[illegible]



MAX. SPAN — 500'
24° — 60°

STANDARD CONFIGURATION
VERTICAL SUSPENSION ANGLE

A3

POWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

REVISIONS _____


ELECTRIC CITIES
OF GEORGIA

DATE: MARCH, 1991

1.04

A3

[illegible]



SINGLE PHASE SUSPENSION

A4

POWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

DATE: MARCH, 1991

REVISIONS


ELECTRIC CITIES
OF GEORGIA

1.05


CONSTRUCTION ASSEMBLY SPECIFICATIONS FOR ELECTRIC CITIES SINGLE PHASE SUSPENSION

A4


[illegible]



TOP VIEW



SECTION X - X



SINGLE PHASE, DEADEND

A5

POWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

REVISIONS


ELECTRIC CITIES
OF GEORGIA

DATE: MARCH, 1991

1.06

SINGLE PHASE, DEADEND

A5[illegible]



SINGLE PHASE DOUBLE DEADEND

A6

OWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

REVISIONS




ELECTRIC CITIES
OF GEORGIA

DATE: MARCH, 1991

1.07

[illegible]

TWO PHASE ASSEMBLIES



Primary separation is to be 36" if adjacent pole is framed horizontal.

24°-60°



TWO PHASE VERTICAL CONSTRUCTION

B3

| | | |
|---|-----------------|-------------------------------|
| WER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA. | REVISIONS _____ | ELECTRIC CITIES
OF GEORGIA |
| DATE: MARCH, 1991 | _____ | 2.04 |

B3

[illegible]



6° - 24°

STANDARD CONFIGURATION MEDIUM LINE ANGLE CONSTRUCTION

B3PA

POWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

REVISIONS _____

ELECTRIC CITIES
OF GEORGIA

DATE: MARCH, 1991



2.05

CONSTRUCTION ASSEMBLY SPECIFICATIONS FOR

ELECTRIC CITIES


STANDARD CONFIGURATION

B3PA[illegible]




TOP VIEW

NOTE:
LOCATE ANCHOR 10' OUTSIDE
OF LINE ANGLE.



80° TO 100°
LINE ANGLE

NOTE:
USE PREDRILLED HOLE
AS SHOWN.



40° TO 80° & 100° TO 150°
LINE ANGLE

NOTE:

1. MAXIMUM SAG AT 60° F. IS
48 INCHES.

STANDARD CONFIGURATION VERTICAL CONSTRUCTION – DOUBLE DEADEND ANGLE

B4

ER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

DATE: MARCH, 1991


REVISIONS _____

ELECTRIC CITIES
OF GEORGIA


2.06

B4


[illegible]



TOP VIEW



SECTION X - X



This configuration to be used
for all two phase deadends
including transformer, arrestor,
and cable riser poles.

Primary conductor separation is to be
36" if adjacent pole is framed horizontal.

TWO PHASE, VERTICAL CONSTRUCTION, DEADEND

B5

OWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

REVISIONS


ELECTRIC CITIES
OF GEORGIA

DATE: MARCH, 1991

2.07

TWO PHASE, VERTICAL CONSTRUCTION, DEADEND

[illegible]



TWO PHASE, VERTICAL CONSTRUCTION, DEADEND

B6

OWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

REVISIONS _____


ELECTRIC CITIES
OF GEORGIA

DATE: MARCH, 1991


2.08

TWO PHASE, VERTICAL CONSTRUCTION, DEADEND

[illegible]



TOP VIEW



STANDARD CONFIGURATION PRIMARY LINE DEADEND

B7S

NOTE:
* MINIMUM OF 72"


POWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

REVISIONS _____

ELECTRIC CITIES
OF GEORGIA

DATE: OCTOBER, 1992

2.10



B8S

STANDARD CONFIGURATION
DOUBLE DEADEND
WIRE SIZE CHANGE

NOTE:

1. DO NOT DOUBLE DEAD END NEUTRAL ON THIS SPECIFICATION. RUN LARGE NEUTRAL TO NEXT POLE FOR DOUBLE DEAD END.
2. LEAVE DOWN GUYS OFF IF WIRE SIZE REMAINS THE SAME

NOTE:

* MINIMUM OF 72"

POWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

REVISIONS _____

ELECTRIC CITIES
OF GEORGIA


DATE: OCTOBER, 1992

2.12


B8S

[illegible]

THREE PHASE ASSEMBLIES



TOP VIEW



This configuration is to be used only between two existing horizontal assemblies.

MAX. SPAN - 500'
0° - 6°

STANDARD CONFIGURATION STRAIGHT LINE CONSTRUCTION

C1S

POWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

REVISIONS


ELECTRIC CITIES
OF GEORGIA

DATE: MARCH, 1991

3.03


CONSTRUCTION ASSEMBLY SPECIFICATIONS
FOR
ELECTRIC CITIES
STANDARD CONFIGURATION
STRAIGHT LINE CONSTRUCTION
C1S

[illegible]



TOP VIEW

This configuration is to be used
only between two existing horizontal
assemblies.



MAX. SPAN - 500'
6° - 24°
STEEL

STANDARD CONFIGURATION SMALL LINE ANGLE CONSTRUCTION

C1PS



JWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

REVISIONS _____

ELECTRIC CITIES
OF GEORGIA

DATE: MARCH, 1991

3.02



Primary conductor separation is to be 36" if an adjacent pole is framed horizontal.

THREE PHASE, VERTICAL CONSTRUCTION, SUSPENSION INSULATORS

C3

OWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

REVISIONS

ELECTRIC CITIES
OF GEORGIA


DATE: MARCH, 1991

3.06


C3

[illegible]

28' 4"



TOP VIEW



Primary conductor separation is to be 36" if an adjacent pole is framed horizontal.

MAX. SPAN - 500'
0° - 6°

ALTERNATE CONFIGURATION VERTICAL STRAIGHT LINE CONSTRUCTION

C3PA

OWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

REVISIONS


ELECTRIC CITIES
OF GEORGIA

DATE: MARCH, 1991

3.07

C3PA

[illegible]



C-3P,E-8
6° - 24°

STANDARD CONFIGURATION
MEDIUM LINE ANGLE CONSTRUCTION
16" BRACKET

— DEMOTES THE USE OF
A PRE-DRILLED HOLE

DRAWN BY: H. BREHEN
SCALE: NOT TO SCALE
DATE: 11-12-87

REVISIONS
APPROVED BY: V. BLACKWOOD


MARIETTA-BLW

C-3P,E-8

BILL OF MATERIAL C-3P,E-8


14.4/24.9 KV, 3-PHASE MEDIUM LINE ANGLE CONSTRUCTION

| QT. # | KEY # | MATERIAL | COST |
|-------|--------|---|------|
| 3 | 96940 | INSULATOR, POST TYPE HORIZONTAL | |
| 3 | 58200 | BRACKET, POST INSULATOR 8" | |
| 7 | 146080 | WASHERS, SQUARE, 2 1/2" | |
| 1 | 97430 | INSULATOR, SPOOL | |
| 1 | 65650 | CLEMS, SECONDARY I-20 | |
| 4 | 57291 | BRACKET, GUY, HOG EAR | |
| 4 | 146100 | 4" X 4" SQUARE CURVED WASHERS | |
| 3 | 97650 | INSULATOR, LINK STICK, 54" | |
| 1 | 122588 | ROD, GROUND | |
| 4 | 124730 | SCREW, LAG | |
| 3 | | CLAMP, BUTTERFLY, SIZE AS REQUIRED | |
| 11 | | BOLT, MACHINE, 5/8" AT REQUIRED LENGTH | |
| 14 | | DEADEND, GUY, PERFORMED, 4 • GROUND | |
| 2 | | ANCHORS, SIZE & TYPE REQ. BY CONDITIONS | |
| 2 | | RODS, ANCHOR, (SIZE AS REQ.) | |
| 1 | | TIE, SPOOL I-20(SIZE AS REQ.) | |
| | | POLE, (SIZE AS REQ.) | |
| | | | |
| | | | |
| | | | |
| | | | |




Primary conductor separation is to be 36" if an adjacent pole is framed horizontal.

NOTE:
1. MAXIMUM SAG AT 60° F. IS 48 INCHES.




TOP VIEW

NOTE:
LOCATE ANCHOR 10' OUTSIDE OF LINE ANGLE.



80° TO 100°
LINE ANGLE

NOTE:
USE PREDRILLED HOLE AS SHOWN.



40° TO 80° & 100° TO 150°
LINE ANGLE

STANDARD CONFIGURATION VERTICAL CONSTRUCTION – DOUBLE DEADEND ANGLE

C4

POWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.


REVISIONS _____

ELECTRIC CITIES
OF GEORGIA


DATE: MARCH, 1991

3.08

[illegible]



TOP VIEW



This configuration is to be used on all three phase deadends including transformer, arrestor, and riser poles.

The primary conductor separation is to be 36" if adjacent pole is framed horizontal.

THREE PHASE, VERTICAL CONSTRUCTION, DEADEND

C5

POWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

REVISIONS _____

ELECTRIC CITIES
OF GEORGIA


DATE: MARCH, 1991

3.09

THREE PHASE, VERTICAL CONSTRUCTION, DEADEND

C5

[illegible]



THREE PHASE, VERTICAL CONSTRUCTION, DEADEND

C6

DWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

REVISIONS


ELECTRIC CITIES
OF GEORGIA

DATE: MARCH, 1991


3.10

THREE PHASE, VERTICAL CONSTRUCTION, DEADEND

[illegible]



TOP VIEW



Primary conductor separation is to be 36" if an adjacent pole is framed horizontal.

1. LINE ANGLE SHOULD EQUAL OR EXCEED 15° TO CLEAR ANCHOR GUYS.
2. IF LINE ANGLE IS LESS THAN 15° THEN HORIZONTAL SLACK SPAN SHOULD BE CONSTRUCTION.

NOTES - GENERAL:

1. SLACK SPAN LENGTH SHOULD BE AS SHORT AS POSSIBLE.
2. SLACK SPAN CONDUCTOR SHOULD BE HAND TENSIONED TO AVOID PULLING OVER THE MAIN LINE POLE.
3. DO NOT USE HORIZONTAL CONSTRUCTION ON ONE POLE AND VERTICAL CONSTRUCTION ON THE OTHER.
4. THREE PHASE LINE CUTOUTS SHOULD NOT BE INSTALLED ON THESE POLES.

SLACK SPAN VERTICAL CONSTRUCTION **C6A**

WER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

REVISIONS


ELECTRIC CITIES
OF GEORGIA

DATE: MARCH, 1991

3.11

SECTION ASSEMBLY SPECIFICATIONS FOR ELECTRIC CITIES SLACK SPAN VERTICAL CONSTRUCTION **C6A**

[illegible]



(RECOMMENDED FOR WIRE LARGER THAN 1/0)

STANDARD CONFIGURATION PRIMARY LINE DEADEND

C7S

NOTE:
* MINIMUM OF 72"

OWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

REVISIONS


ELECTRIC CITIES
OF GEORGIA

DATE: OCTOBER, 1992

3.13

CONSTRUCTION ASSEMBLY SPECIFICATIONS
FOR
ELECTRIC CITIES
STANDARD CONFIGURATION
PRIMARY LINE DEADEND
C7S

[illegible]




STANDARD CONFIGURATION
DOUBLE DEADEND
WIRE SIZE CHANGE

1. DO NOT DOUBLE DEAD END NEUTRAL ON THIS SPECIFICATION. RUN LARGE NEUTRAL TO NEXT POLE FOR DOUBLE DEAD END.
2. LEAVE DOWN GUYS OFF IF WIRE SIZE REMAINS THE SAME

3.16

CBS

[illegible]



C-1,A-5

SINGLE PHASE FUSED PRIMARY LINE PULL OFF

NOTE:

1. MAXIMUM PULL OFF CONDUCTOR SIZE - 4/0 ACSR.
2. USE CUTOUTS WITH LOADBUSTER HOOKS ONLY.
3. IF NORMAL OPEN POINT, REMOVE FUSE BARRELS AND STORE IN UP RIGHT POSITION ON POLE.

--DENOTES THE USE OF A PRE-DRILLED HOLE

AWN BY: H. BREHEN

SCALE: NOT TO SCALE

DATE: 11-18-87

REVISIONS

APPROVED BY: V. BLACKWOOD

MARIETTA-BLW


C-1,A-5

BILL OF MATERIAL

C-1,A-5

SINGLE PHASE FUSED PRIMARY LINE PULL OFF

| QT. # | KEY # | MATERIAL | COST |
|-------|--------|--|------|
| 3 | 96800 | INSULATOR, SUSPENSION | |
| 7 | 146080 | WASHERS, SQUARE, 2 1/2" | |
| 1 | 97430 | INSULATOR, SPOOL | |
| 1 | 65650 | CLEVIS, SECONDARY I-20 | |
| 2 | 57291 | BRACKET, GUY GRIP HOG EAR | |
| 2 | 146100 | 4" X 4" SQUARE CURVED WASHERS | |
| 1 | 57250 | BRACKET, "T" HANGER | |
| 1 | 97650 | INSULATOR, LINK STICK, 54" | |
| 1 | 112480 | PIN, POLE TOP | |
| 1 | 97220 | INSULATOR, SADDLE BACK | |
| 1 | 122588 | ROD, GROUND | |
| 3 | 124730 | SCREW, LAG | |
| 1 | 46670 | ARM, 2 POST INSULATOR | |
| 2 | 97710 | INSULATOR, POST TYPE, TIE TOP | |
| 1 | 78880 | CUTOUTS, 100A OPEN TYPE | |
| 1 | | DEADEND SHOES, SIZE AS REQUIRED | |
| 7 | | BOLT, MACHINE 5/8" AT REQUIRED LENGTH | |
| 1 | | TIE, SPOOL I-20 (SIZE AS REQ.) | |
| 2 | | TIE, PRIMARY, SIDE TYPE (SIZE AS REQ.) | |
| 1 | | TIE, PRIMARY, CEN. POSITION (SIZE AS REQ.) | |
| 1 | | DEADEND, DIST GRIP SPOOL (SIZE AS REQ.) | |
| 1 | | ANCHOR, SIZE & TYPE REQ. BY CONDITIONS | |
| 1 | | ROD, ANCHOR SIZE AS REQUIRED | |
| 6 | | DEADEND, GUY, PREFORMED, 2" GROUND | |
| 1 | | POLE SIZE AS REQUIRED | |
| 1 | | BOLT, EYE 5/8" (SIZE AS REQ.) | |



This configuration is to be used only on existing horizontal assemblies.

STANDARD CONFIGURATION PRIMARY LINE PULL-OFF

NOTE:
1. INSTALL DEAD END ARM PERPENDICULAR TO PULL OFF.

— DENOTES THE USE OF A PRE-DRILLED HOLE

DRAWN BY: H. BREHEN

REVISIONS

MARIETTA-BLW

SCALE: NOT TO SCALE

APPROVED BY: V. BLACKWOOD

C-1, C-7


DATE: 11-25-87

BILL OF MATERIAL

C-1,C-7

PRIMARY LINE PULL-OFF

| QT. # | KEY # | MATERIAL | COST |
|-------|--------|--|------|
| 9 | 96800 | INSULATOR, SUSPENSION | |
| 1 | 112480 | PIN, POLE TOP | |
| 1 | 97220 | INSULATOR, SADDLEBACK | |
| 9 | 146080 | WASHERS, SQUARE, 2 1/2" | |
| 1 | 97430 | INSULATOR, SPOOL | |
| 1 | 65650 | CLEVIS, SECONDARY I-20 | |
| 3 | 57291 | BRACKET, GUY GRIP, HOG EAR | |
| 1 | 46670 | ARM, TWO POST INSULATORS | |
| 3 | 14610 | 4" X 4" SQUARE CURVED WASHERS | |
| 4 | 97710 | INSULATOR, POST TYPE | |
| 2 | 97650 | INSULATOR, LINK STICK, 54" | |
| 3 | 124730 | SCREW, LAG | |
| 1 | 122588 | ROD, GROUND | |
| 1 | 46675 | ARM, 5' STEEL | |
| 1 | | TIE, SPOOL I-20 (SIZE AS REQ.) | |
| 10 | | DEADEND, GUY, PREFORMED, 3 @ GROUND | |
| 1 | | EYE BOLT, 5/8" AT REQUIRED LENGTH | |
| 3 | | DEADEND SHOES, SIZE AS REQUIRED | |
| 9 | | BOLT, MACHINE, 5/8" AT REQUIRED LENGTH | |
| 1 | | TIE, PRIMARY, CEN. POSITION (SIZE AS REQ.) | |
| 1 | | ANCHOR, SIZE & TYPE REQ. BY CONDITIONS | |
| 2 | | ROD, ANCHOR (SIZE AS REQ.) | |
| 2 | | DEADEND, DIST. GRIP SPOOL (SIZE AS REQ.) | |
| 1 | | BOLT, 3/4" D.A. (SIZE AS REQ.) | |
| 1 | | POLE, (SIZE AS REQUIRED) | |
| 2 | | TIE, PRIMARY, SIDE TYPE (SIZE AS REQ.) | |



STANDARD CONFIGURATION
PRIMARY LINE PULL-OFF
8" ARM

— DENOTES THE USE OF
A PRE-DRILLED HOLE

DRAWN BY: H. BREHEN
SCALE: NOT TO SCALE
DATE: 11-25-87

REVISIONS
APPROVED BY: V. BLACKWOOD

MARIETTA-BLW

C-3P, C-5

BILL OF MATERIAL


C-3P,C-5

14.4/24.9 KV, 3-PHASE PRIMARY LINE PULL-OFF

| QT. # | KEY # | MATERIAL | COST |
|-------|--------|---|------|
| 9 | 96800 | INSULATOR, SUSPENSION | |
| 4 | 146100 | 4" X 4" SQUARE CURVED WASHERS | |
| 13 | 146080 | WASHERS, SQUARE, 2 1/2" | |
| 1 | 97430 | INSULATOR, SPOOL | |
| 1 | 65650 | CLEVIS, SECONDARY I-20 | |
| 4 | 57291 | BRACKET, GUY GRIP, HOG EARS | |
| 3 | 97650 | INSULATOR, LINK STICK, 54" | |
| 3 | 97710 | INSULATORS, POST, TIE TOP | |
| 3 | 58200 | BRACKET, POST INSULATOR 8" | |
| 4 | 124730 | SCREW, LAG | |
| 1 | 122588 | ROD, GROUND | |
| 2 | | ANCHOR, SIZE & TYPE REQ. BY CONDITIONS | |
| 2 | | ROD, ANCHOR (SIZE AS REQ.) | |
| 1 | | TIE, SPOOL I-20 (SIZE AS REQ.) | |
| 3 | | DEADEND SHOES, SIZE AS REQUIRED | |
| 11 | | BOLT, MACHINE, 5/8" AT REQUIRED LENGTH | |
| 14 | | DEADEND, GUY, PREFORMED, 2 @ GROUND | |
| 3 | | TIE, PRIMARY, SIDE TYPE (SIZE AS REQ.) | |
| 3 | | EYE BOLT, 5/8" AT REQUIRED LENGTH | |
| 1 | | DEADEND, DIST GRIP SPOOL (SIZE AS REQ.) | |
| 1 | | POLE, (SIZE AS REQUIRED) | |

POST INSULATOR CONSTRUCTION
VERTICAL CROSSOVER WOOD POLE
13 & 23 kV

E-5.3.1





WOOD POLE
30 VERTICAL CROSSOVER
FIGURE 1

NOTES:

1. ALL POST INSULATORS SHOWN ARE 35KV TIE TOP. USE CLAMP TOPS WHERE INDICATED BY ANGLE AND SIDE PULL LIMITATIONS SHOWN ON E-4. USE 45KV POST INSULATORS (CLAMP TYPE) ON 23KV CIRCUITS IN SALT CONTAMINATED AREAS.
2. PRIMARY TO NEUTRAL SEPARATION AT POLE IS DETERMINED BY MINIMUM MIDSPAN SEPARATION (DERM 4.4.1). IN NO CASE SHALL SEPARATION AT POLE BE LESS THAN 60" FOR WOOD POLES 40" FOR CONCRETE POLES.
3. "MINIMUM" DIMENSIONS MAY BE USED TO AVOID POLE CHANGEOUT OR EXCESSIVE GRADING TO A TALLER POLE.

SUPERSEDES E-5.3 LAST REVISED ON 3-1-89
STANDARDS
OH & UG DISTRIBUTION SYSTEM
FLORIDA POWER & LIGHT COMPANY

| | | | | | | | | | | |
|-----|------|----------|------|-----|------|------|------|---|--------------------------|--|
| NO. | DATE | REVISION | H.O. | OR. | DES. | O.D. | APP. | ORIG. A.B.R.
DRAWN: LOZADA/FLARCO
(DES) F.W.H. (ODS) JEB
CHECKED | NO SCALE
DATE: 1-1-81 | APPROVED
R.K. CIELO
DIRECTOR, DISTRIBUTION ENGINEERING
AND SERVICE PLANNING |
|-----|------|----------|------|-----|------|------|------|---|--------------------------|--|



. TIE TOP INSULATORS
0° - 6°

DOUBLE CIRCUIT CONSTRUCTION STRAIGHT LINE & SMALL ANGLE

DC-C1

•-DENOTES THE USE OF
A PRE-DRILLED HOLE

POWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

REVISIONS _____


ELECTRIC CITIES
OF GEORGIA

4.02

DATE: MARCH, 1991

DC-C1 (4.02)

[illegible]



CLAMP TOP INSULATORS
6° - 24°

DOUBLE CIRCUIT CONSTRUCTION STRAIGHT LINE & SMALL ANGLE

DC-C1P

NOTE:
* OPTIONAL 30"

POWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

REVISIONS _____

ELECTRIC CITIES
OF GEORGIA


DATE: OCTOBER, 1992

4.01

CONSTRUCTION ASSEMBLY SPECIFICATIONS
FOR
ELECTRIC CITIES
HORIZONTAL DEAD END
DOUBLE CURCUIT DEADEND CONSTRUCTION
DC-C7

[illegible]

FOR TRANSFORMER CONNECTIONS REFER TO PAGES
3.70, 3.71, 3.72, 7.33, 3.74



THREE TRANSFORMER INSTALLATION

DRAWN BY A.A.W.B.
TRACED BY A.A.W.B.
APPROVED: *[Signature]*


DATE 12/18/81
SCALE NONE

REVISIONS 12-15-88 8-1-88
09-14-90

GEORGIA POWER COMPANY

C-428-GO

FOR TRANSFORMER CONNECTIONS REFER TO PAGES
13.70, 3.71, 3.72, 3.73, 3.74



NOTES

1. ON CLOSED WYE-DELTA BANKS, DO NOT CONNECT BANK PRIMARY NEUTRAL TO SYSTEM NEUTRAL OR POLE GROUND.
2. ON WYE-WYE BANKS, CONNECT BANK PRIMARY NEUTRAL AND SECONDARY NEUTRAL TO SYSTEM NEUTRAL.
3. FOR MULTIPLE SERVICES - USE COPPER TRANSFORMER LEADS.
4. FOR ONE SERVICE - CONNECT SERVICE CONDUCTOR TO TRANSFORMER BUSHINGS.
5. ANCHOR GUY LEAD LENGTH SHOULD BE A MINIMUM OF 22 FEET.
6. SEE PAGE No. 190 FOR ANCHOR GUY AND GUY STRAIN INSULATOR INSTALLATION.

THREE TRANSFORMER INSTALLATION HORIZONTAL DEAD END POLE

• - DENOTES THE USE OF
PRE-DRILLED HOLES.

DRAWN BY A.A.W.B.

DATE 12-23-81

REVISIONS 0-4-84 12-15-88

GEORGIA POWER COMPANY

TRACED BY A.A.W.B.


SCALE NONE

09-14-90

APPROVED *[Signature]*

COM00061

FOR TRANSFORMER CONNECTIONS REFER TO PAGES
73.70, 3.71, 3.72, 3.73, 3.74



NOTES

1. ON CLOSED-WYE-DELTA BANKS, DO NOT CONNECT BANK PRIMARY NEUTRAL TO SYSTEM NEUTRAL OR POLE GROUND.
2. ON WYE-WYE BANKS, CONNECT BANK PRIMARY NEUTRAL AND SECONDARY NEUTRAL TO SYSTEM NEUTRAL.
3. FOR MULTIPLE SERVICES - USE COPPER TRANSFORMER LEADS.
4. FOR ONE SERVICE - CONNECT SERVICE CONDUCTOR TO TRANSFORMER BUSHINGS.
5. ANCHOR GUY LEAD LENGTH SHOULD BE A MINIMUM OF 22 FEET.
6. SEE PAGE No. 1.90 FOR ANCHOR GUY AND GUY STRAIN INSULATOR INSTALLATION.

THREE TRANSFORMER INSTALLATION VERTICAL DEAD END POLE

• - DENOTES THE USE OF
PRE-DRILLED HOLES.

DRAWN BY A.A.W.B.

DATE 12-23-81

REVISIONS 8-4-84 12-15-88

GEORGIA POWER COMPANY

TRACED BY A.A.W.B.

SCALE NONE

09-14-90


APPROVED

C. C. Bledsoe

COM00062

OIL CIRCUIT RECLOSER WITH BY-PASS

[illegible]




THREE PHASE OIL CIRCUIT RECLOSER OR SECTIONALIZER

ARMLESS CONSTRUCTION
THREE PHASE INSTALLATION

- NOTES:
1. COVER CAN BE ROTATED 180° TO ORIENT BUSHINGS AND HOOD IN DESIRED POSITION.
 2. TYPE R, V, W, VV, RX, OCR'S RECLOSE ELECTRICALLY FROM INTERNAL CLOSING COIL. BUSHING MARKED "SOURCE" MUST BE CONNECTED TO THE SOURCE LINE, AND THE GROUND TERMINAL GROUNDED.
 3. INSTALL ARRESTERS AT SOURCE AND LOAD BUSHINGS.
 4. WHERE POSSIBLE THE OCR SHOULD BE FRAMED TO POSITION THE OPERATING HANDLE TOWARD THE STREET.
 5. LOCATE SWITCH NUMBER ON THE STREET SIDE OF POLE 8' ABOVE GROUND LEVEL.
 6. ARRESTER MOUNTING BRACKETS CAN BE OBTAINED AT FOREST PARK SALVAGE. TURN THE FOUR (4) OUTSIDE ARRESTERS 30° TO THE OUTSIDE.

SECTION A-A



REFER TO NOTE 6

FRONT VIEW

SIDE VIEW

N5463
RED & WHITE ENAMEL
LOCATION NUMBER


DETAIL NO. 1

DRAWN BY J.W.S. B C.S.J. DATE 4-25-75
TRACED BY C.S.J. SCALE NONE
APPROVED *[Signature]*

REVISIONS 1-1-76, 1-10-79, 12-15-88

GEORGIA POWER COMPANY

C-395-GO



This switch is to be used only between two existing horizontal assemblies.

M3-15 THREE PHASE GANG OPERATED HORIZONTAL SWITCH

POWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

DATE: MARCH, 1991


REVISIONS

ELECTRIC CITIES
OF GEORGIA

6.03

M3-15

[illegible]



THREE PHASE GANG OPERATED VERTICAL SWITCH

M3-15V

DJWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

REVISIONS _____


ELECTRIC CITIES
OF GEORGIA

DATE: MARCH, 1991


6.04

M3-15V

[illegible]



FRONT VIEW



SIDE VIEW

BRIDGES IN-LINE SWITCHES

M3-3S

POWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

DATE: MARCH, 1991

REVISIONS _____


ELECTRIC CITIES
OF GEORGIA

6.02

M3-3S

[illegible]

#2 STRAND COPPER



M5-9

INSTALLATION OF SECTIONALIZING SWITCHES FUSED TYPE

NOTE:

1. MAXIMUM PULL OFF CONDUCTOR SIZE - 1/0 ACSR.
2. USE CUTOUTS WITH LOADBUSTER HOOKS ONLY.
3. IF NORMAL OPEN POINT, REMOVE FUSE BARRELS AND STORE IN UPRIGHT POSITION ON POLE.

←-DENOTES THE USE OF
A PRE-DRILLED HOLE

POWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

DATE: MARCH, 1991

REVISIONS

ELECTRIC CITIES
OF GEORGIA


6.07

M5-9

[illegible]

NOTE:

1. THE TERMINAL BUSHING CONNECTED DIRECTLY TO THE COIL SHOULD BE CONNECTED TO THE SOURCE. WHERE NECESSARY TO PROVIDE FOR THIS CONNECTION THE RECLOSER MAY BE MOUNTED ON THE OTHER SIDE OF THE POLE AND THE NEUTRAL DEADENDED.
2. ON ANGLE POLE IN CONFLICT WITH GUY, MOUNT CUTOUT ABOVE RECLOSER.
3. HANG SOLID BLADE OR FUSE HOLDER ON POLE. (SIZE AS REQUIRED)



OIL CIRCUIT RECLOSER WITH BY-PASS

M3-23A

POWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

REVISIONS _____

ELECTRIC CITIES
OF GEORGIA

DATE: MARCH, 1991

6.05

Appr. 150 % rated KVA

Kearney
Type
KS

TABLE 1

PRIMARY FUSE SIZE FOR SINGLE-PHASE TRANSFORMER

| INDIVIDUAL
TRANSFORMER
SIZE - KVA | TRANSFORMER AND SYSTEM VOLTAGE - KV | | | | | | |
|---|-------------------------------------|------------------|--------|---------|------------------------------|-----------|----------|
| | 2.4 | 4.8 | 7.2 | 8.0 | 12.0 | 13.8 | 14.4 |
| | 2.4Δ
24/4Y | 4.8Δ
4.8/8.3Y | 7.2/12 | 8/13.8Y | 12.0A
7.2/12Y
120/20.0 | 8.0/13.8Y | 14.4/25Y |
| 3 | 2 | 1 | 1 | 1 | 1 | 1 | 1 |
| 5 | 3 | 1.5 | 1 | 1 | 1 | 1 | 1 |
| 7.5 | 5 | 2.5 | 1.5 | 1.5 | 1 | 1 | 1 |
| 10 | 7 | 3 | 2 | 2 | 1.5 | 1 | 1 |
| 15 | 10 | 5 | 3 | 3 | 2 | 2 | 1.5 |
| 25 | 15 | 7 | 5 | 5 | 3 | 3 | 2.5 |
| 37.5 | 25 | 10 | 7 | 7 | 5 | 4 | 4 |
| 50 | 30 | 15 | 10 | 10 | 7 | 5 | 5 |
| 75 | 50 | 25 | 15 | 15 | 10 | 7 | 7 |
| 100 | 65 | 30 | 20 | 20 | 15 | 10 | 10 |
| 150 | 80 | 50 | 25 | 25 | 20 | 15 | 15 |
| 167 | 80 | 50 | 30 | 25 | 20 | 15 | 15 |

Not
used
2.08
3.47
5.20
6.94
0.41
3.88
20.83
23.19

↑ 1200 volt

TABLE 2

PRIMARY FUSE SIZE FOR THREE-PHASE BANKS

| INDIVIDUAL
TRANSFORMER
SIZE - KVA | SYSTEM VOLTAGE - KV | | | | | |
|---|---------------------|---------------------|------------|-------------|-------------|-------------|
| | 2.4 | 4.0Y | 4.8 OPEN Δ | 12.0 Y OR Δ | 12.0 OPEN Δ | 25Y |
| | CLOSED Δ | 4.8 Δ
2.4 OPEN Δ | 8.3Y | 13.8 Y OR Δ | 20.0 | 13.8 OPEN Δ |
| 3 | 4 | 2 | 1 | 1 | 1 | 1 |
| 5 | 5 | 3 | 1.5 | 1 | 1 | 1 |
| 7.5 | 10 | 5 | 2.5 | 1.5 | 1 | 1 |
| 10 | 10 | 7 | 3 | 2 | 1.5 | 1 |
| 15 | 15 | 10 | 5 | 3 | 2 | 1.5 |
| 25 | 25 | 15 | 7 | 5 | 3 | 2.5 |
| 37.5 | 40 | 25 | 10 | 7 | 5 | 4 |
| 50 | 50 | 30 | 15 | 10 | 7 | 5 |
| 75 | 65 | 50 | 25 | 15 | 10 | 7 |
| 100 | 80 | 65 | 30 | 20 | 15 | 10 |
| 150 | 100 | 80 | 50 | 25 | 20 | 15 |
| 167 | 100 | 80 | 50 | 30 | 20 | 15 |
| 250 | - | - | - | 40 | 30 | 20 |

Not
s

NOTE:

WHEN ONE FUSE IS BLOWN ON AN INSTALLATION, INSTALL NEW FUSE LINKS IN ALL PHASES OF THAT INSTALLATION.

PRIMARY FUSE SIZE FOR DISTRIBUTION TRANSFORMERS
KEARNEY FUSE LINKS

| | | | | | | |
|-------------|--------------------|-------------|--------|--------------------|----------|-----------------------|
| DRAWN BY | C.D.O. | DATE | 2-1-68 | REVISIONS | 2-14-72, | GEORGIA POWER COMPANY |
| DESIGNED BY | C.S.J. | SCALE | NONE | 7-6-77 | | |
| APPROVED | <i>[Signature]</i> | KPC 2-24-72 | | <i>[Signature]</i> | | |
| | | | | | | A-368-GO |

Joe
from PE study.
Same as GPC chart.
JCB

CITY OF LAGRANGE ELECTRIC SYSTEM


TRANSFORMER FUSE CHART
USE ONLY TYPE "KS" FUSES

SINGLE PHASE AND IN BANKS

| <u>SIZE</u>
<u>KVA</u> | <u>12.47/7.2 KV</u>
<u>FUSE AMPS</u> |
|---------------------------|---|
| 5 | 1 |
| 10 | 2 |
| 15 | 3 |
| 25 | 5 |
| 37 | 7 |
| 50 | 10 |
| 75 | 15 |
| 100 | 20 |
| 150 | 25 |
| 167 | 30 |
| 333 | 35 |
| 500 | 50 |

THREE PHASE

| <u>SIZE</u>
<u>KVA</u> | <u>12.47/7.2 KV</u>
<u>FUSE AMPS</u> |
|---------------------------|---|
| 150 | 8 |
| 300 | 15 |
| 500 | 25 |
| 750 | 30 |
| 1000 | 35 |
| 1500 | 50 |
| 2500 | 80 |



| SECONDARY LEAD SIZE | | |
|---------------------|----------------|--|
| TRANS. SIZE | MIN. LEAD SIZE | |
| 15 KVA | 1/0 CU. | |
| 25 KVA | 1/0 CU. | |
| 37.5 KVA | 2/0 CU. | |
| 75 KVA | 4/0 CU. | |
| 100 KVA | 500 CU. | |

G110


SINGLE TRANSFORMER INSTALLATION

- NOTES:
1. CONNECT TRANSFORMER SECONDARY NEUTRAL LEAD TO SYSTEM AND LEAVE APPROXIMATELY 12 INCH TAIL FOR SERVICE NEUTRAL CONNECTIONS.
 2. IF ONLY ONE SERVICE IS TO BE INSTALLED, THE SERVICE NEUTRAL SHOULD BE CONNECTED TO THE SYSTEM NEUTRAL AND TERMINATED AT THE TRANSFORMER SECONDARY NEUTRAL TERMINAL WITH A SERV-EN ADAPTER, THE PHASE CONDUCTORS SHOULD BE CONNECTED TO THE TRANSFORMER SECONDARY TERMINALS WITH SERV-EN ADAPTERS.
 3. IF SECONDARY IS TO EXTEND IN LINE, EXTEND PRIMARY WIRE TO ELIMINATE CONFLICT BETWEEN SECONDARY AND ANCHOR GUY. IF IT IS NOT DESIRABLE TO EXTEND PRIMARY INSTALL SPAN GUY TO NEXT POLE.
 - * 4. Separation between bottom phase and neutral will be 72" minimum.

CONSTRUCTION ASSEMBLY SPECIFICATIONS
FOR
ELECTRIC CITIES
SINGLE TRANSFORMER INSTALLATION DEADEND POLE

[illegible]

FOR TRANSFORMER CONNECTIONS REFER TO PAGES
73.70, 3.71, 3.72, 3.73, 3.74



NOTES

1. ON CLOSED WYE-DELTA BANKS, DO NOT CONNECT BANK PRIMARY NEUTRAL TO SYSTEM NEUTRAL OR POLE GROUND.
2. ON WYE-WYE BANKS, CONNECT BANK PRIMARY NEUTRAL AND SECONDARY NEUTRAL TO SYSTEM NEUTRAL.
3. FOR MULTIPLE SERVICES - USE COPPER TRANSFORMER LEADS.
4. FOR ONE SERVICE - CONNECT SERVICE CONDUCTOR TO TRANSFORMER BUSHINGS.
5. ANCHOR GUY LEAD LENGTH SHOULD BE A MINIMUM OF 22 FEET.
6. SEE PAGE No. 1.90 FOR ANCHOR GUY AND GUY STRAIN INSULATOR INSTALLATION.

THREE TRANSFORMER INSTALLATION VERTICAL DEAD END POLE

• - DENOTES THE USE OF
PRE-DRILLED HOLES.

DRAWN BY A.A.W.B. DATE 12-23-81
TRACED BY A.A.W.B. SCALE NONE
APPROVED C.C. Bentley

REVISIONS 6-4-84 12-15-88
09-14-90

GEORGIA POWER COMPANY

COM00062

NEUTRAL


30" min to lowest primary

24"

NOTE:
USE 110 MIL INSULATED WIRE.

PRI. AND SECONDARY
MUST BE INTERCONNECTED

12.5/7.2 KV.



SECONDARY LEAD SIZE

| TRANS. SIZE | MIN. LEAD SIZE |
|-------------|----------------|
| 15 KVA | 1/0 CU. |
| 25 KVA | 1/0 CU. |
| 37.5 KVA | 2/0 CU. |
| 75 KVA | 4/0 CU. |
| 100 KVA | 500 CU. |

MIN. 6"

G312

THREE TRANSFORMERS CLUSTER MOUNTED
FOUR WIRE GROUND WYE - GROUND WYE

POWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.


DATE: MARCH, 1991

REVISIONS

ELECTRIC CITIES
OF GEORGIA

7.04

FOR TRANSFORMER CONNECTIONS REFER TO PAGES
13.70, 3.71, 3.72, 3.73, 3.74



NOTES

1. ON CLOSED WYE-DELTA BANKS, DO NOT CONNECT BANK PRIMARY NEUTRAL TO SYSTEM NEUTRAL OR POLE GROUND.
2. ON WYE-WYE BANKS, CONNECT BANK PRIMARY NEUTRAL AND SECONDARY NEUTRAL TO SYSTEM NEUTRAL.
3. FOR MULTIPLE SERVICES - USE COPPER TRANSFORMER LEADS.
4. FOR ONE SERVICE - CONNECT SERVICE CONDUCTOR TO TRANSFORMER BUSHINGS.
5. ANCHOR GUY LEAD LENGTH SHOULD BE A MINIMUM OF 22 FEET.
6. SEE PAGE No. 190 FOR ANCHOR GUY AND GUY STRAIN INSULATOR INSTALLATION.

THREE TRANSFORMER INSTALLATION HORIZONTAL DEAD END POLE

• - DENOTES THE USE OF
PRE-DRILLED HOLES.


DRAWN BY A.A.W.B. DATE 12-23-81
TRACED BY A.A.W.B. SCALE NONE
APPROVED [Signature]

REVISIONS 6-4-84 12-15-86
09-14-90

GEORGIA POWER COMPANY

COM00061

FOR TRANSFORMER CONNECTIONS REFER TO PAGES
3.70, 3.71, 3.72, 7.33, 3.74



- NOTE:**
- ON CLOSED WYE-DELTA BANKS, DO NOT CONNECT BANK PRIMARY NEUTRAL TO SYSTEM NEUTRAL OR POLE GROUND.
 - ON WYE-WYE BANKS, CONNECT BANK PRIMARY NEUTRAL AND SECONDARY NEUTRAL TO SYSTEM NEUTRAL.
 - FOR MULTIPLE SERVICES - USE COPPER TRANSFORMER LEADS.
 - FOR ONE SERVICE - CONNECT SERVICE CONDUCTOR TO TRANSFORMER BUSHINGS.

THREE TRANSFORMER INSTALLATION

* - DENOTES THE USE OF PRE-DRILLED HOLE.

DRAWN BY A.A.W.B. DATE 12/18/81
 TRACED BY A.A.W.B. SCALE NONE
 APPROVED [Signature]

REVISIONS 12-15-86 8-1-88
09-14-90

GEORGIA POWER COMPANY

C-428-GO

CONSTRUCTION ASSEMBLY SPECIFICATIONS
FOR
ELECTRIC CITIES

THREE TRANSFORMERS CLUSTER MOUNTED
FOUR WIRE GROUNDED WYE - GROUNDED WYE

[illegible]

City of LaGrange Utilities **Memo**

To: Joe
From: Patrick
Date: Sunday, April 21, 1996
Subject: Ungrounded Wye-Delta Banks

This memo is to follow up on our discussion about "floating" the primary on a wye-delta transformer bank. After doing a little research, I believe this is a good suggestion for us to implement. The advantages are as follows:

- ✓ Eliminates the tendency of the bank to supply single phase faults (and loads) in the vicinity.
- ✓ Reduces the magnitude of single phase faults near the bank..
- ✓ No longer need to worry about transformer overload due to undetected blown fuse which creates an open-wye bank.

There are a few precautions that must be considered:

- Dual bushing transformers must be used (since we only buy these, this will not be a problem)
- Care must be used to ensure that the neutral wiring on the primary side is sufficiently isolated from ground.
- The customer will experience a single-phase condition if one of the primary supply lines is interrupted.

You might want to go over this change with your employees at your next meeting to be sure they understand the situation. Sounds like your idea is a good one!

UNDERGROUND CONSTRUCTION


CABLE TAGS

PRIMARY TAGS

○ ○
TO PAD #
OR
TO POTHEAD #

NOTES:

1. IF TRANSFORMER IS NORMAL OPEN POINT, COVERS MUST BE CONNECTED TO GROUND.
2. LEAVE CABLE CONCENTRIC NEUTRAL LONG ENOUGH TO ALLOW ELBOW SWITCHING.
3. CONNECT BUSHINGS TO TANK GROUND WITH ONE (1) STRAND OF CONCENTRIC NEUTRAL.
4. CONCENTRIC NEUTRAL AND BARE COPPER NEUTRAL TO BE LOOPED AND RAN ALONG BOTTOM EDGE OF TRANSFORMER.



UG17-2
UG18-2

THREE PHASE PAD MOUNTED TRANSFORMER
LOOP FEED

OWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

REVISIONS

ELECTRIC CITIES
OF GEORGIA

9.01


DATE: MARCH, 1991

CONSTRUCTION ASSEMBLY SPECIFICATIONS
FOR
ELECTRIC CITIES
THREE PHASE PAD MOUNTED TRANSFORMER
LOOP FEED
UG17-2
UG18-2


[illegible]

CABLE TAGS


PRIMARY TAGS



SERVICE TAGS




EXTERNALLY
REMOVABLE
FUSE



NOTES:

1. THE CONCENTRIC NEUTRAL HAS TO BE LOOPED UP TO FAULT IND. AND BACK DOWN CABLE.
2. H-1 IS ALWAYS THE SOURCE.



UG6

SINGLE PHASE PAD MOUNTED TRANSFORMER CONNECTIONS DETAILS, LOOP FEED

POWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

DATE: MARCH, 1991

REVISIONS

ELECTRIC CITIES
OF GEORGIA

9.02


CONSTRUCTION ASSEMBLY SPECIFICATIONS FOR

ELECTRIC CITIES

SINGLE PHASE PAD MOUNTED TRANSFORMER CONNECTION DETAILS, LOOP FEED

UG6

[illegible]




THREE PHASE POTHEAD POLE WITH RISER

UM2-5A



| | | |
|---|------------------|---|
| <p>OWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.</p> <p>DATE: MARCH, 1991</p> | <p>REVISIONS</p> | <p>ELECTRIC CITIES
OF GEORGIA</p> <p>9.09</p> |
|---|------------------|---|

THREE PHASE POTHEAD POLE WITH RISER

[illegible]



SECTION X-X



UM2-9A
 THREE PHASE POTHEAD INSTALLATION
 FOR 1000 ~~XL~~ U.G. FEEDER
 EPR

POWER ENGINEERING ASSOCIATES, INC.
 MARIETTA, GA.

DATE: MARCH, 1991


REVISIONS _____

ELECTRIC CITIES
 OF GEORGIA


9.10

CONSTRUCTION ASSEMBLY SPECIFICATIONS
FOR
ELECTRIC CITIES
THREE PHASE POTHEAD INSTALLATION
FOR 1000 XLP U.G. FEEDER
UM2-9A



| ITEM | QUANTITY | STOCK NO. | MATERIAL | |
|------|----------|-----------|---|--|
| | 3 | | ARRESTER, RISER POLE I | |
| | 1 | | BRACKET, 3 PH. ARR. & CUTOUT LARGE | |
| | 1 | | 5/8" EYE BOLT | |
| | 6 | | NUT, LOCK 5/8" | |
| | 1 | | SCREW, LAG 1/2" X 4" | |
| | 6 | | WASHER, SQUARE 2 1/2" X 2 1/2" | |
| | 3 | | GRIP, CABLE RISER 750 | |
| | 1 | | GUARD, CABLE W/VENT 5" WITH BACKING PLATE | |
| | 3 | | TERMINATOR, 1000 MCM 25 kV | |
| | 3 | | SWITCHES IN LINE | |
| | 6 | | DEADEND, CLAMP, SIZE AS REQUIRED | |
| | 6 | | BOLT SQUARE ON CONNECTORS FOR SWITCHES | |
| | 1 | | PIN, POLE TOP F/POST INS. | |
| | 1 | | INSULATOR, CLAMP TOP POST VERTICAL | |
| | 2 | | INSULATOR, CLAMP TOP POST HORIZONTAL | |
| | 3 | | CLAMP, F/POST INSULATOR, SIZE AS REQUIRED | |
| | 1 | | CLEVIS, SHACKLE F/KELLUM GRIP | |
| | 3 | | KELLUM GRIPS, F/1000 MCM WIRE | |
| | 5 | | BOLTS, MACHINE 5/8", SIZE AS REQUIRED | |
| | AS REQ'D | | GUARD, CABLE | |
| | 1 | | CLEVIS, SECONDARY | |
| | 1 | | INSULATOR, SPOOL | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |
| | | | | |




OPEN 600 AMP VIEW
(DOORS REMOVED FOR CLARITY)



OPEN FUSED VIEW
(DOORS REMOVED FOR CLARITY)



NOTE: FOR GANG OPERATED SWITCHING CUBICLES EACH GANG SWITCH NUMBER SHALL BE INSTALLED IMMEDIATELY ADJACENT TO THE APPROPRIATE OPERATING HANDLE COMPARTMENT.



PAD MOUNTED SWITCHING CUBICLE WITH PAD FOR 15 KV.
THREE PHASE PRIMARY GANG - OPERATED 600 AMP.
DISCONNECTS WITH FUSED TAPS

UM53-3-9

POWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

DATE: MARCH, 1991

REVISIONS

ELECTRIC CITIES
OF GEORGIA


9.12

UM53-3-9

[illegible]

NOTES:

1. MIN. #6 COPPER TO BE PLACED IN DITCH WITH PRIMARY CABLE.
2. GROUND RESISTANCE SHOULD BE MEASURED AND REDUCED TO 25 OHMS, IF POSSIBLE.



GROUNDING DETAILS FOR PAD MOUNTED TRANSFORMERS



POWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

REVISIONS _____

ELECTRIC CITIES
OF GEORGIA

DATE: OCTOBER, 1992


9.03



NOTE:
DESIGNATE AS UM1 - PLASTIC PAD

PLASTIC PAD ASSEMBLY **UM1**

| | | |
|---|-----------------|-------------------------------|
| POWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA. | REVISIONS _____ | ELECTRIC CITIES
OF GEORGIA |
| DATE: <u>OCTOBER, 1992</u> | _____ | 9.04 |



NOTES:

1. SERVICE DUCT SHALL BE LOCATED IN THE EXTREME RIGHT SIDE OF THE SECONDARY COMPARTMENT.
2. PRIMARY DUCT SHALL EXTEND BEYOND EDGE OF PAD IN DIRECTION OF INCOMING PRIMARY CABLES.
3. MATERIAL FOR PRIMARY DUCT SYSTEM WILL BE FURNISHED BY GEORGIA POWER COMPANY.
4. THE PAD SHALL HAVE A MINIMUM CLEARANCE OF 10' FROM ALL BUILDINGS. TO PROVIDE SUFFICIENT COOLING. A MINIMUM CLEARANCE OF 3' SHALL BE MAINTAINED FROM ALL OBSTRUCTIONS.
5. REINFORCE WITH #4 BARS WITH A 12"x12" GRID. 4" BELOW TOP OF PAD.
6. CONCRETE SHALL HAVE A MINIMUM ULTIMATE 28 DAY COMPRESSIVE STRENGTH OF NOT LESS THAN 3,000 POUNDS. PAD SHALL BE CURED NOT LESS THAN 72 HOURS.

STANDARD PAD FOR 150-1000 KVA RADIAL OR LOOP FEED PAD MOUNTED TRANSFORMERS


POWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

REVISIONS

ELECTRIC CITIES
OF GEORGIA

DATE: OCTOBER, 1992

9.06





NOTES:

1. PAD ASSEMBLIES INCLUDE SITE PREPARATION, BEDDING AND DRAINAGE.
2. SLABS MAY BE PRECAST OR POURED IN PLACE. CONCRETE SHALL BE A 1:2:4 MIXTURE WITH A MINIMUM DESIGN STRENGTH OF 3000 P.S.I. STEEL REINFORCING SHALL BE 6" X 6" - NO. 10 WIRE MESH TO STOP 1" FROM SIDES AND CABLE OPENING.
3. EQUIPMENT SHALL BE SECURED TO PAD IN ACCORDANCE WITH MANUFACTURER'S INSTRUCTIONS.
4. LOCATION AND SIZE OF CABLE OPENING SHALL BE AS REQUIRED FOR CABLE RUN.

CONCRETE PAD ASSEMBLY

UM1-C

| | | |
|---|-----------------|-------------------------------|
| POWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA. | REVISIONS _____ | ELECTRIC CITIES
OF GEORGIA |
| DATE: <u>OCTOBER, 1992</u> | _____ | 9.05 |



NOTE:


1. CONDUIT SHOULD BE 2" ABOVE PAD WITH PLASTIC BUSHINGS.
2. PRECAST PAD FOR 112 KVA TO 1500 KVA TRANSFORMERS.

THREE PHASE PRECAST
LARGE PAD SPECIFICATION

UM1-5

| | | |
|---|-----------------------------------|-------------------------------|
| POWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA. | REVISIONS _____

_____ | ELECTRIC CITIES
OF GEORGIA |
| DATE: <u>OCTOBER, 1992</u> | | 9.07 |



TRANSFORMER CONNECTOR BLOCKS

UJ2-4 THRU UJ2-8

| | | |
|---|-----------------------------------|-------------------------------|
| POWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA. | REVISIONS _____

_____ | ELECTRIC CITIES
OF GEORGIA |
| DATE: <u>OCTOBER, 1992</u> | | 9.08 |

**ELECTRIC SERVICE
AND
METER INSTALLATIONS**

A. GENERAL NOTES

1. OVERHEAD SERVICE DROP AND METER PROVIDED AND INSTALLED BY COMPANY.
2. METER SOCKET PROVIDED (NORMALLY) BY COMPANY, AND INSTALLED BY CUSTOMER.
3. CLEARANCES MUST BE PROVIDED AS SHOWN BELOW.
4. METER SOCKET SHOULD BE "READILY ACCESSIBLE" (SEE DEFINITIONS Pg. 5.002)
AND ALLOW WORKSPACE AS ILLUSTRATED BELOW.
5. REFER TO PAGES 5.120 THRU 5.123 FOR REQUIREMENTS REGARDING CUSTOMER OWNED
SOCKETS.

B. MOUNTING OF METER SOCKET


1. UNIT SHALL BE SURFACE MOUNTED , WITH CENTER OF UNIT BETWEEN 2' 6" AND 6' ABOVE FINAL GRADE, IN A LEVEL AND PLUMB POSITION.
2. UNIT SHALL BE FASTENED TO BUILDING SECURELY USING LEAD ANCHORS (FOR BRICK AND CONCRETE), TOGGLE BOLTS (FOR WOOD SIDING) OR WOOD SCREWS (FOR 2"x4" STUDS, LOG WALLS, OR OTHER SOLID LUMBER). ALL SCREWS OR BOLTS SHALL BE 1/4" DIAMETER (MIN.) STAINLESS STEEL. A MINIMUM OF FOUR FASTENERS SHALL BE USED TO MOUNT SOCKET.

C. SERVICE DROP ATTACHMENT

1. DEVICE FOR ATTACHING SERVICE DROP TO BUILDING SHALL BE FURNISHED BY COMPANY AND INSTALLED SECURELY BY CUSTOMER (SEE PAGE 5.105) AT MINIMUM VERTICAL CLEARANCE AS SHOWN BELOW.
2. IF MINIMUM VERTICAL CLEARANCE CANNOT BE MAINTAINED WITH THE INSTALLATION OF AN ATTACHMENT BOLT AS SHOWN BELOW, THE CUSTOMER SHALL INSTALL A STEEL SERVICE MAST (SEE PAGE 5.105).
3. CONNECTIONS BETWEEN SERVICE DROP AND SERVICE ENTRANCE CONDUCTORS SHALL BE MADE (BY COMPANY PERSONNEL) BELOW WEATHERHEAD, FORMING A DRIP LOOP.

D. CONNECTIONS IN METER SOCKET

1. REFER TO PAGES 5.112 THRU 5.165 FOR METER SOCKET CONNECTION INSTRUCTIONS.



TYPICAL RESIDENTIAL OVERHEAD INSTALLATION


DRAWN BY A.A.W.B. DATE 4/1/88
 TRACED BY A.A.W.B. SCALE NONE
 APPROVED CC [Signature] W.S. [Signature]

REVISIONS

GEORGIA POWER COMPANY

C-545-GO

EYE BOLT (B4500 THROUGH (B4780) OR TOGGLE BOLT 14"(B6820) OR 24"(B6840). CUSTOMER SHOULD EXTEND BOLT THROUGH FACIA TO ROOF JOIST, RAFTER, OR SOLID LUMBER AND FASTEN SECURELY. DO NOT USE THREAD-THRU INSULATOR OR SCREW TYPE HOOK.



GENERAL NOTES:

1. DEVICE FOR ATTACHING SERVICE DROP TO BUILDING FURNISHED BY COMPANY AND INSTALLED SECURELY BY CUSTOMER AS NOTED ABOVE.
2. CONNECTIONS BETWEEN SERVICE ENTRANCE CONDUCTORS AND SERVICE DROP SHALL BE MADE (BY COMPANY PERSONNEL) BELOW WEATHERHEAD, FORMING A DRIP LOOP.
3. SEE PAGE 5.101 FOR VERTICAL CLEARANCE REQUIREMENTS BETWEEN SERVICE AND FINAL GRADE LEVEL

TRIPLEX SERVICE INSTALLATION

DRAWN BY A.A.W.B.

DATE 10-30-80

REVISIONS 4/1/88


GEORGIA POWER COMPANY

TRACED BY

SCALE NONE

APPROVED

A-478-GO



A. GENERAL NOTES

1. TYPICAL SINGLE PHASE RESIDENTIAL INSTALLATION SHOWN.
2. SINGLE PHASE COMMERCIAL AND SELF CONTAINED 30-200 AMP. COMMERCIAL CAN BE INSTALLED AS SHOWN. COMMERCIAL BUILDING ROOF DESIGNS MAY DIFFER FROM ROOF DESIGN SHOWN.
3. REFER TO PAGES 5.112 THRU 5.185 FOR TYPICAL METER INSTALLATION.

B. MAST HEIGHT AND LOCATION

1. MASTS TALLER THAN 36 INCHES ABOVE ROOF SHALL BE GUYED.
2. THE LENGTH OF SERVICE DROP EXTENDING OVER ROOF (INCLUDING EAVES AND GUTTERS) SHALL NOT EXCEED 48 INCHES.

C. CONNECTIONS IN METER SOCKET

REFER TO PAGES 5.112 THRU 5.185 FOR REQUIREMENT AND RESTRICTIONS.


TYPICAL STEEL SERVICE MAST INSTALLATION (FURNISHED AND INSTALLED BY CUSTOMER)


DRAWN BY A.A.W.B. DATE 4/1/88
 TRACED BY A.A.W.B. SCALE NONE
 APPROVED [Signature]

REVISIONS _____


GEORGIA POWER COMPANY

COM00015



NOTE: CROSSHATCHED  AREA DENOTES UNDISTURBED OR RE-COMPACTED SOIL DIRECTLY BENEATH CABLE (EXTENDING 36\"/>

TYPICAL RESIDENTIAL UNDERGROUND INSTALLATION

| | | | | | |
|-----------|---|-------|--------|-----------|-----------------------|
| DRAWN BY | A.A.W.B. | DATE | 4/1/88 | REVISIONS | GEORGIA POWER COMPANY |
| TRACED BY | A.A.W.B. | SCALE | NONE | | |
| APPROVED |  | | | | A-529-GO |

**CURRENT TRANSFORMER INSTALLATION ON
MAST BRACKET QUADRAPLEX SERVICE
COMPANY-OWNED METER SOCKET (M-2392)**

A. GENERAL NOTES


1. This arrangement might be utilized on services above 200 amperes where deemed appropriate by a qualified employee of the Company.
2. Overhead service drop and meter provided and installed by Company.
3. Current transformers provided by company and may be issued to the customer for installation or installed by company employees.
4. Meter socket provided by Company and installed by customer.
5. One inch metal or intermediate metal conduit and service mast furnished and installed by customer as illustrated on page 5.147.
6. Metering control cable provided and installed by Company.
7. The applicable requirements for this installation regarding accessibility to equipment, unobstructed working space adjacent to enclosures, and clearances are specified on pages 5.101 and 5.147.
8. The length of service drop over roof shall not exceed 48"
9. Placement of meter socket in alley ways or areas where meter is subject to damage shall require advance approval of division meter supervisor.

B. MOUNTING

1. Socket and 1" conduit shall be surface mounted with center of socket located as shown on page 5.147.
2. Meter socket and conduit straps shall be fastened to building using lead anchors (brick or solid masonry), toggle bolts (other masonry, siding), or wood screws (studs, solid lumber). All screws shall be 1/4" minimum diameter stainless steel. A minimum of four (4) fasteners shall be used to mount meter socket.

C. CONNECTIONS

1. All connections shall be made by Company.
2. Conduit shall be bonded to meter socket with proper bonding bushing furnished and installed by customer.
3. Grounding electrode conductors shall not originate, pass through, or be attached to meter socket.




CURRENT TRANSFORMER INSTALLATION ON MAST BRACKET - QUADRAPLEX SERVICE COMPANY OWNED METER SOCKET (M2392)

DRAWN BY A.A.W.B. DATE 4/1/88
 TRACED BY A.A.W.B. SCALE NONE
 APPROVED [Signature]

REVISIONS _____

GEORGIA POWER COMPANY

A-534-GO



DRAWN BY G.W.B. DATE 12-15-66
 TRACED BY G.W.B. SCALE
 APPROVED [Signature] 1-4-67

REVISIONS 12-19-66
11-20-67, 6-12-68, 3-5-71,
12-12-75, 2-1-81, 4-1-88

GEORGIA POWER COMPANY

A-304-GO

**TRANSFORMER RATED UNDERGROUND METER SOCKET
3-WIRE SINGLE-PHASE 1200 AMP SERVICE
COMPANY-OWNED METER SOCKET (M-2630)**

A. GENERAL NOTES


1. This arrangement is to be utilized for residential and commercial services above 200 amps up to 1200 amps only where deemed appropriate by a qualified employee of the Company.
2. Service entrance load conductors, conduit, conduit straps, lock nuts, bushings, box connectors, and miscellaneous mounting hardware are to be furnished and installed by the customer.
3. Meter socket provided (normally) by Company and installed by customer.
4. Meter, control cable, and underground service lateral provided and installed by Company. Customer to provide approximate final grade level within six inches (6") prior to underground service lateral installation.
5. Current transformers provided by company and may be issued to the customer for installation or installed by company employees.
6. The applicable requirements regarding accessibility to equipment and unobstructed working space adjacent to enclosures are specified on page 5.101.
7. Placement of meter socket in alley ways or areas where meter is subject to damage shall require advance approval of division meter supervisor.

B. MOUNTING

1. Meter socket and conduit shall be surface mounted as specified on page 5.107.
2. Meter socket and conduit straps shall be fastened to building using lead anchors (brick or solid masonry), toggle bolts (other masonry, siding), or wood screws (studs, solid lumber). All screws, bolts shall be 3/8" diameter (minimum) stainless steel. A minimum of four (4) fasteners shall be used to mount socket.
3. Six inch (6') trade size rigid steel galvanized conduit or schedule 40 PVC shall be furnished and installed by customer as specified on page 5.107.
4. Conduit end shall be equipped with a proper bushing to protect cables.

C. CONNECTIONS

1. Company will wire brush and apply non-grit type inhibitor to all line and load conductors and terminate by using tubular to flat compression connectors and terminate by torquing to 200 inch pounds.
2. Grounding electrode conductors shall not originate, pass through, or be attached to meter socket.



1200 AMP MAXIMUM
SERVICE

**TRANSFORMER RATED UNDERGROUND METER
SOCKET FOR 3 WIRE SINGLE PHASE
SERVICE 1200 AMP MAXIMUM
COMPANY - OWNED SOCKET (M-2630)**

DRAWN BY A.A.W.B. DATE 4/1/88
TRACED BY A.A.W.B. SCALE NONE
APPROVED *[Signature]*

REVISIONS _____

GEORGIA POWER COMPANY
COM00024

TYPICAL UNDERGROUND COMMERCIAL THREE-PHASE INSTALLATION WITH MULTIPLE CUSTOMERS ON COMMON SERVICE LATERAL

A. GENERAL NOTES

1. Conductors, conduit, conduit straps, lock nuts, bushings, box connectors, and miscellaneous mounting hardware are to be furnished and installed by the customer.
2. Meter sockets provided (normally) by Company and installed by customer.
3. The applicable requirements regarding accessibility to equipment and unobstructed working space adjacent to enclosures are specified on page 5.101.
4. Refer to pages 5.120 through 5.123 for requirements regarding customer-owned meter sockets.
5. Placement of meter socket in alley ways or areas where meter is subject to damage shall require advance approval of division meter supervisor.

B. MOUNTING


1. Meter sockets, cabinets, trough, and conduits shall be surface mounted as specified.
2. Meter socket, current transformer cabinet, and conduit straps shall be fastened to building using lead anchors (brick or solid masonry), toggle bolts (other masonry, siding), or wood screws (studs, solid lumber). All screws, bolts shall be 1/4" diameter (minimum) stainless steel. A minimum of four (4) fasteners shall be used to mount socket and cabinet.
3. Conduit ends shall be equipped with a proper bushing to protect control cables.

C. CONNECTIONS

1. Customer shall terminate the conductors inside the customers' equipment.
2. Company will make all service lateral connections at pole or padmount transformer.
3. Grounding electrode conductors shall not originate, pass through, or be attached to meter socket.

D. MARKING

1. Each socket position and the corresponding building unit to be served (suite, apartment, street, or office number shall be accurately, clearly, and permanently labeled before meters are installed.
2. Letters/numbers shall be minimum 1" in height, enamel paint, of contrasting color to that of the sockets.



NOTE.

1. METER SOCKET MOUNTED OUTDOORS EXCEPT WHERE SPECIAL PERMISSION OBTAINED FROM QUALIFIED EMPLOYEE OF COMPANY.
2. COMPANY TO MAKE ALL SERVICE LATERAL CONNECTIONS AT POLE OR PADMOUNT TRANSFORMER AND ALL METERING CONTROL CABLE CONNECTION'S IN METER SOCKET AND C.T. CABINET. CUSTOMER TO MAKE ALL CONNECTION'S IN WIRE TROUGH.
3. CONDUCTOR CARRYING METERED AND UNMETERED ENERGY SHALL NOT BE ALLOWED IN SAME WIRING TROUGH OR CONDUIT.

TYPICAL UNDERGROUND COMMERCIAL 3Ø INSTALLATION WITH MULTIPLE CUSTOMERS ON COMMON SERVICE LATERAL

DRAWN BY A.A.W.B. DATE 4/1/88
 TRACED BY A.A.W.B. SCALE NONE
 APPROVED *[Signature]*

REVISIONS _____

GEORGIA POWER COMPANY

COM00008

UNDERGROUND COMMERCIAL THREE-PHASE TRANSFORMER RATED METER INSTALLATION WITH ONLY ONE CUSTOMER

A. GENERAL NOTES

1. Conductors, conduit, conduit straps, lock nuts, bushings, box connectors, and miscellaneous mounting hardware are to be furnished and installed by the customer.
2. Meter socket and pedestal provided (normally) by Company and installed by customer.
3. Meter and current transformers provided and installed by Company.
4. The applicable requirements regarding accessibility to equipment and unobstructed working space adjacent to enclosures are specified on Page 5.101.
5. Placement of meter socket in alley ways or areas where meter is subject to damage shall require advance approval of division meter supervisor.

B. MOUNTING


1. Meter socket and conduit straps shall be fastened to the pedestal using bolts. Bolts shall be 1/4" diameter (minimum) stainless steel.
2. Conduit end shall be equipped with a proper bushing to protect control cables.

C. CONNECTIONS

1. Customer shall terminate the conductors inside the customer's equipment.
2. Company will make all service lateral connections at padmount transformer.
3. Grounding electrode conductors shall not originate, pass through, or be attached to meter socket.

NOTES

1. THIS METHOD OF SERVICE MUST BE APPROVED BY A QUALIFIED COMPANY EMPLOYEE
2. METER SOCKET MOUNTED OUTDOORS ON A PEDESTAL OR OUTSIDE WALL OF BUILDING.
3. COMPANY TO MAKE ALL SERVICE LATERAL CONNECTIONS AT PADMOUNT TRANSFORMER AND CONNECTION INSIDE METER SOCKET AND SECONDARY COMPARTMENT OF TRANSFORMER.
4. C.T.s TO BE INSTALLED IN SECONDARY COMPARTMENT OF THE PADMOUNT TRANSFORMER BY A QUALIFIED EMPLOYEE.
5. THIS METHOD OF SERVICE IS TYPICAL WHEN ONLY ONE 3Ø CUSTOMER IS SERVED FROM A PADMOUNT TRANSFORMER.
6. METER AND/OR METER CABINET SHALL NOT BE MOUNTED ONTO THE PADMOUNT TRANSFORMER.
7. IF PROBABILITY EXISTS FOR MORE THAN ONE CUSTOMER TO BE SERVED FROM THE PADMOUNT TRANSFORMER USE METHOD OF SERVICE SHOWN ON PAGES 5.157 AND 5.159.



UNDERGROUND COMMERCIAL 3Ø TRANSFORMER RATED METER INSTALLATION WITH ONLY ONE CUSTOMER

DRAWN BY A.A.W.B. DATE 4/1/88
 TRACED BY A.A.W.B. SCALE NONE
 APPROVED *[Signature]*

REVISIONS _____

GEORGIA POWER COMPANY
COM00023

**UNDERGROUND INDUSTRIAL THREE-PHASE TRANSFORMER
RATED METER INSTALLATION WITH ONLY ONE CUSTOMER
480 V TRANSFORMER 500 KVA AND ABOVE**

A. GENERAL NOTES

1. Conductors, conduit, conduit straps, lock nuts, bushings, box connectors, and miscellaneous mounting hardware are to be furnished and installed by the customer.
2. Meter socket and pedestal provided (normally) by Company and installed by customer.
3. Meter, current transformers, and voltage transformers provided and installed by Company.
4. The applicable requirements regarding accessibility to meter equipment and unobstructed working space adjacent to meter enclosures are specified on Page 5.101.
5. Placement of meter socket in alley ways or areas where meter is subject to damage shall require advance approval of division meter supervisor.

B. MOUNTING


1. Meter socket and conduit straps shall be fastened to the pedestal using bolts. Bolts shall be 1/4" diameter (minimum) stainless steel.
2. Conduit end shall be equipped with a proper bushing to protect cables.

C. CONNECTIONS

1. Customer shall terminate the conductors inside the customer's equipment.
2. Company will make all service lateral connections at padmount transformer.
3. Grounding electrode conductors shall not originate, pass through, or be attached to meter socket.

NOTE

1. POTENTIAL TRANSFORMER BRACKET AND MOUNTING PADS SHALL BE INCLUDED ON ALL 480V TRANSFORMERS 500 kVA AND ABOVE.
2. METER SOCKET MOUNTED ON A PEDESTAL OR OUTSIDE WALL OF BUILDING.
3. COMPANY TO MAKE ALL SERVICE LATERAL CONNECTIONS AT PADMOUNT TRANSFORMER AND CONTROL CABLE CONNECTIONS INSIDE METER SOCKET AND SECONDARY COMPARTMENT OF TRANSFORMER.
4. P.T.s AND C.T.s TO BE INSTALLED IN SECONDARY COMPARTMENT OF THE PADMOUNT TRANSFORMER BY A QUALIFIED EMPLOYEE.
5. THIS METHOD OF SERVICE IS TYPICAL WHEN ONLY ONE 3Ø CUSTOMER IS SERVED FROM A PADMOUNT TRANSFORMER.
6. METER AND/OR METER CABINET SHALL NOT BE MOUNTED ONTO THE PADMOUNT TRANSFORMER.
7. METER PEDESTAL NORMALLY FURNISHED BY COMPANY, INSTALLED AND MAINTAINED BY CUSTOMER.
8. METER CABINET AND/OR METER SOCKET M2392 FURNISHED BY COMPANY AND INSTALLED BY CUSTOMER.



UNDERGROUND INDUSTRIAL 3Ø TRANSFORMER RATED METER INSTALLATION WITH ONLY ONE CUSTOMER 480V TRANSFORMER 500kVA AND ABOVE

DRAWN BY A.A.W.B. DATE 4/1/88
 TRACED BY A.A.W.B. SCALE NONE
 APPROVED *A.A.W.B.*

REVISIONS _____

GEORGIA POWER COMPANY
COM00021

**SECONDARY
DESIGN**

All secondary installations shall be designed to satisfy the following critereaa:

1. Transformers and conductors within capacity limits.
2. Total transformer, secondary, and service voltage drop limited to 6%.
3. Voltage flicker due to motor starting limited to 6.5%.

EXAMPLE

A 60 KVA 120/208 volt three phase load with the largest motor rated at 7 1/2 HP is supplied by 3 X 25 KVA transformers and 150 feet of 2/0 Al quadruplex service drop.

Capacity Calculation:

Load = 167 Amps

Transformer Rating = 208 Amps (capable of 333 Amps)

Conductor Rating = 205 Amps

Voltage Drop Calculation:

Transformer = 1.25% from Table

Conductor = 150/100 feet x 0.037 x 60 KVA = 3.33%

Total = 4.58% (less than 6% limit)

Flicker Calculation

Assume motor starting KVA is 7 times the rated HP.

Starting KVA = 7 x 7.5 HP = 53 KVA


Drop in Conductor = 150/100 x 0.037 x 53 KVA = 2.94%

Drop in Transformer = 3.15% from Table

Total = 6.09% (less than 6.5% limit)

PROPERTIES OF ALUMINUM
SERVICE CABLE WITH
FULL ACSR NEUTRAL

| SIZE
(AWG) | CONFIG | STRENGTH
(LB) | WEIGHT
(LB/1000') | CAPACITY | | IMPEDANCE | | % VOLTAGE DROP
PER KVA PER 100 FT | | |
|---------------|-------------------------|------------------|----------------------|--------------------------|----------|-----------------|-----------------|--------------------------------------|---------|-----------|
| | | | | OVERHEAD/
DIRECT BURY | IN DUCTS | R
(OHM/100') | X
(OHM/100') | 120/240 | 120/208 | 240-DELTA |
| 336.4 | QUADRUPLER SERVICE DROP | 8680 | 1631.9 | 370 | N/A | 0.00624 | 0.00343 | | 0.016 | 0.012 |
| 4/0 | QUADRUPLER SERVICE DROP | 8350 | 1079.1 | 275 | N/A | 0.00981 | 0.00362 | | 0.024 | 0.018 |
| 2/0 | QUADRUPLER SERVICE DROP | 5310 | 707.2 | 205 | N/A | 0.01545 | 0.00379 | | 0.037 | 0.028 |
| 4/0 | TRIPLEX SERVICE DROP | 8350 | 816.4 | 315 | N/A | 0.00981 | 0.00362 | 0.036 | | |
| 2/0 | TRIPLEX SERVICE DROP | 5310 | 544.0 | 235 | N/A | 0.01545 | 0.00379 | 0.055 | | |
| 1/0 | TRIPLEX SERVICE DROP | 4380 | 432.0 | 205 | N/A | 0.01951 | 0.00392 | 0.069 | | |
| #2 | TRIPLEX SERVICE DROP | 2850 | 272.2 | 150 | N/A | 0.03106 | 0.00434 | 0.109 | | |
| #4 | TRIPLEX SERVICE DROP | 1860 | 180.0 | 115 | N/A | 0.04886 | 0.00466 | 0.170 | | |
| #4 | DUPLEX SERVICE DROP | 1860 | 118.8 | 115 | N/A | 0.04886 | 0.00466 | 0.170 | | |
| #6 | DUPLEX SERVICE DROP | 1190 | 80.3 | 85 | N/A | 0.07822 | 0.00489 | 0.272 | | |
| 4/0 | QUADRAPLEX 600V UD | | 1128.8 | 290 | 225 | 0.00981 | 0.00589 | | 0.026 | 0.020 |
| 4/0 | TRIPLEX 600V UD | | 846.7 | 315 | 240 | 0.00981 | 0.00589 | 0.040 | | |
| 1/0 | TRIPLEX 600V UD | | 475.8 | 215 | 160 | 0.01951 | 0.00684 | 0.072 | | |
| #4 | TRIPLEX 600V UD | | 206.1 | 126 | 90 | 0.04886 | 0.00813 | 0.172 | | |



PERCENT DROP VERSUS KVA LOAD
FOR TYPICAL TRANSFORMERS

DRAWN BY J. J. S. DATE 11-11-60
 TRACED BY J. P. T. SCALE NONE
 APPROVED W. K. R. 12-29-69

REVISIONS 1-1-65
12-29-69

NUMBER
A-307-G.O.

CALCULATION OF SECONDARY FLICKER AND VOLTAGE DROP DUE TO STARTING AND RUNNING SMALL 1 ϕ 240V. MOTORS

**STARTING VOLTAGE DROP
CONTRIBUTION OF TRANSFORMER = T% DROP PER H.P.**

| TRANSFORMER
SIZE | % STARTING DROP
PER H.P. |
|---------------------|-----------------------------|
| 10 KVA | T = 1.10% |
| 15 KVA | T = 0.71% |
| 25 KVA | T = 0.42% |
| 37.5 KVA | T = 0.27% |
| 50 KVA | T = 0.19% |
| 75 KVA | T = 0.13% |
| 100 KVA | T = 0.10% |

**STARTING VOLTAGE DROP
CONTRIBUTION OF CONDUCTOR = C% DROP PER 100 FT. PER H.P.**

| CONDUCTOR
SIZE | % STARTING DROP
PER H.P. |
|------------------------|-----------------------------|
| N ϕ 2 ACSR | C = 0.74% |
| N ϕ 1/0 ACSR | C = 0.54% |
| N ϕ 4/0 ACSR | C = 0.35% |
| N ϕ 2 PAC OR TA | C = 0.57% |
| N ϕ 1/0 PAC OR TA | C = 0.37% |
| N ϕ 4/0 PAC OR TA | C = 0.20% |

SECONDARY STARTING
VOLTAGE DROP = MOTOR RATED H.P. $\left[T + C \left(\frac{\text{CONDUCTOR LENGTH}}{100} \right) \right]$

SECONDARY RUNNING = SECONDARY STARTING VOLTAGE DROP
VOLTAGE DROP 5.62

EXAMPLE

5 H.P., 240V. MOTOR
25 KVA TRANSFORMER
135 FT. N ϕ 1/0 TA

% STARTING DROP = $5 [0.42 + 0.37 (1.35)]$
STARTING DROP = 4.6%

RUNNING DROP = $\frac{4.6}{5.62} = 0.82\%$

NOTE: IF MOTOR RATED HORSEPOWER IS NOT KNOWN, THE FOLLOWING APPROXIMATIONS
MAY BE USED:

$$\text{MOTOR RATED HP} = \frac{\text{BTU/HR CAPACITY}}{7400} = 1.6 \text{ (TONNAGE CAPACITY)}$$

$$= \frac{\text{RUNNING AMPS}}{4.7} = \frac{\text{STARTING AMPS}}{28}$$

CALCULATIONS ARE FOR A TYPE "G" MOTOR WITH 6.29 INRUSH KVA PER H.P.

DRAWN BY J.J.S. DATE 1-15-69
TRACED BY B.G.H. SCALE NONE
APPROVED *[Signature]* 2-1-69

REVISIONS 2-1-69
7-1-70

GEORGIA POWER COMPANY

A-415-60

**POLE AND GUY
SIZING**

| TRANSFORMER KVA | | 3 | 5 | 7.5 | 10 | 15 | 25 | 37.5 | 50 | 75 | 100 | 167 | 250 |
|-----------------------------|------------|---|---|-----|----|----|----|------|----|----|-----|-----|-----|
| SINGLE PHASE | | | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 4 | 4 | 3 | 1 |
| | | | | | | | | | | | | | |
| BANKS OF TWO TRANSFORMERS | 3 KVA | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 4 | 4 | 3 | 1 |
| | 5 KVA | | 5 | 5 | 5 | 5 | 5 | 5 | 5 | 4 | 4 | 3 | 1 |
| | 7.5 KVA | | | 5 | 5 | 5 | 5 | 5 | 4 | 4 | 4 | 3 | 1 |
| | 10 KVA | | | | 5 | 5 | 5 | 5 | 4 | 4 | 4 | 3 | 1 |
| | 15 KVA | | | | | 5 | 5 | 5 | 4 | 4 | 4 | 3 | 1 |
| | 25 KVA | | | | | | 5 | 4 | 3 | 3 | 3 | 3 | 1 |
| | 37.5 KVA | | | | | | | 3 | 3 | 3 | 3 | 3 | 1 |
| | 50 KVA | | | | | | | | 3 | 3 | 3 | 3 | 1 |
| | 75 KVA | | | | | | | | | 3 | 3 | 2 | 1 |
| | 100 KVA | | | | | | | | | | 3 | 2 | 1 |
| | 167 KVA | | | | | | | | | | | 2 | 1 |
| | 250 KVA | | | | | | | | | | | | 1 |
| BANKS OF THREE TRANSFORMERS | | | | | | | | | | | | | |
| | 2-3 KVA | 5 | 5 | | | | | | | | | | |
| | 2-5 KVA | | 5 | 5 | 5 | | | | | | | | |
| | 2-7.5 KVA | | | 5 | 5 | 5 | | | | | | | |
| | 2-10 KVA | | | | 5 | 5 | | | | | | | |
| | 2-15 KVA | | | | | 4 | 4 | | | | | | |
| | 2-25 KVA | | | | | | 4 | 4 | 3 | | | | |
| | 2-37.5 KVA | | | | | | | 3 | 3 | 3 | | | |
| | 2-50 KVA | | | | | | | | 3 | 3 | 2 | | |
| | 2-75 KVA | | | | | | | | | 2 | 2 | | |
| | 2-100 KVA | | | | | | | | | | 2 | 2 | |
| | 2-167 KVA | | | | | | | | | | | 2 | 1 |
| | 2-250 KVA | | | | | | | | | | | | 1 |

EXAMPLES: 1. FIND CLASS OF POLE REQUIRED FOR BANK OF 1-25 KVA & 1-10 KVA TRANSFORMER. LOOK IN 25 KVA VERTICAL COLUMN AND 10 KVA HORIZONTAL COLUMN OPPOSITE BANKS OF TWO TRANSFORMERS. RESULT: CLASS 5 POLE.

2. FOR 2-15 AND 1-25 LOOK IN 25 KVA VERTICAL COLUMN AND 2-15 KVA HORIZONTAL COLUMN OPPOSITE BANKS OF THREE TRANSFORMERS. RESULT: CLASS 4 POLE.

EXCEPTIONS: 1. THIS TABLE IS FOR NEW CONSTRUCTION. WHERE POLE IN PLACE IS NOT OVER ONE CLASS SMALLER, DO NOT CHANGE.


2. WHEN INSTALLING TRANSFORMERS WITH CAST IRON CASES. USE POLE ONE CLASS LARGER THAN SHOWN ABOVE.

RECOMMENDED CLASS OF POLE FOR TRANSFORMER INSTALLATION ON SINGLE POLE - ALL VOLTAGES.

| | | | |
|-----------------------------|---------------------|-----------------|---------------------------|
| DRAWN BY <u>H.G.B.</u> | DATE <u>4-22-65</u> | REVISIONS _____ | NUMBER
A-298-GO |
| TRACED BY <u>C.R.S.</u> | SCALE _____ | _____ | |
| APPROVED <u>[Signature]</u> | | _____ | |

TOTAL MAXIMUM TENSION
IN ALL CONDUCTORS
(SEE PAGE 11.60)

| GUY WIRE
SIZE | NUMBER
OF STRANDS | MAXIMUM
TENSION (LBS) |
|------------------|----------------------|--------------------------|
| 5/16" | 7 | 6,000 |
| 3/8" | 7 | 11,500 |
| 7/16" | 7 | 18,000 |



| RATIO OF X/Y | MULTIPLIER |
|--------------|------------|
| 0 * | 1.49 |
| .5 | 1.67 |
| 1.0 | 2.11 |
| 1.5 | 2.69 |
| 2.0 | 3.34 |
| 2.5 | 4.02 |
| 3.0 | 4.72 |

*HEAD GUY

GUYING STRENGTH NECESSARY = TOTAL MAXIMUM TENSION X MULTIPLIER

EXAMPLE: FIGURE GUYING STRENGTH NECESSARY TO HOLD
3 NO. 1/0 ACSR AND 1 NO. 2 ACSR. GUY ATTACHMENT IS 32' ABOVE
GROUND. ANCHOR IS TO BE 22' FROM POLE.
MAXIMUM TENSION = $3 \times 2034 + 1800 = 7902$ LBS.
RATIO OF X/Y = $32/22 = 1.45$
GUYING NECESSARY $2.69 \times 7902 = 21,256$ LBS.
THEREFORE USE (2) 11.5M GUYS.

DEAD END GUYING TABLE

| | | | |
|-----------------------------------|------------------------|-----------------|----------|
| DRAWN BY <u>J.C.H.</u> | DATE <u>SEPT. 1964</u> | REVISIONS _____ | NUMBER |
| TRACED BY <u>C.R.S.</u> | SCALE _____ | _____ | A-341-GO |
| APPROVED <u>ECB</u> <u>1-1-65</u> | _____ | _____ | |

| | STRINGING TENSIONS(LBS) | | | | MAXIMUM
LOADED
TENSION * |
|--------------|-------------------------|------|------|------|--------------------------------|
| TEMP. °F | 45° | 60° | 75° | 90° | |
| WIRE SIZE | A.C.S.R. | | | | |
| 636 MCM | 1713 | 1659 | 1609 | 1562 | 3276 |
| 336.4MCM | 1260 | 1206 | 1158 | 1110 | 3000 |
| 4/0 | 797 | 762 | 730 | 701 | 2616 |
| 1/0 | 397 | 380 | 364 | 349 | 2034 |
| 2 | 292 | 280 | 268 | 257 | 1800 |
| 2 PVC | 464 | 449 | 436 | 423 | 1776 |
| 1/0PVC | 624 | 605 | 586 | 569 | 1992 |
| 4/0PVC | 1009 | 978 | 948 | 920 | 2496 |
| 336.4MCM PVC | 1402 | 1358 | 1317 | 1278 | 3000 |
| | | | | | |
| COPPER | | | | | |
| 4/0 | 1452 | 1307 | 1188 | 1089 | 3000 |
| 1/0 | 724 | 651 | 592 | 543 | 2238 |
| 2 | 446 | 402 | 365 | 335 | 1750 |
| 3 | 354 | 319 | 290 | 265 | 1500 |
| 2 PVC | 544 | 504 | 470 | 440 | 1776 |
| | | | | | |
| TRIPLEX | | | | | |
| 4/0 TRI. | 921 | 882 | 847 | 815 | 2280 |
| 1/0 TRI. | 498 | 477 | 458 | 441 | 1668 |
| | | | | | |
| | | | | | |
| | | | | | |

* USE FOR DETERMINING GUYING STRENGTH.

CONDUCTOR TENSION TABLE

| | | | |
|---------------------------------|-----------------------|-----------------|--------------|
| DRAWN BY <u>EC.B.</u> | DATE <u>DEC. 1984</u> | REVISIONS _____ | NUMBER _____ |
| TRACED BY <u>C.R.S.</u> | SCALE _____ | _____ | A-350-GO |
| APPROVED <u>EC.B. CB 1-1-85</u> | | _____ | |

ANCHORING APPLICATION GUIDE

| SOIL CLASS NO. | SOIL CLASSIFICATION | TYPE ANCHORS (MATERIAL NO.) | | | | | 10" SWAMP ANCHOR | ROCK ANCHOR 3/4" DIA. ROD |
|----------------|---|-----------------------------|----------|----------------|-----------|----------------------|------------------|---------------------------|
| | | 8" EXPANDING SCREW | 8" SCREW | 11 5/16" SCREW | 8" SQUARE | HOLDING POWER IN LBS | | |
| CLASS 1 | ROCK | 23,000 | 23,000 | 23,000 | 23,000 | 23,000 | * | 23,000 |
| CLASS 2 | HARDPAN: VERY DENSE SAND: SANDSTONE | 23,000 | 23,000 | 23,000 | 23,000 | 23,000 | * | * |
| CLASS 3 | HARDCLAY: DENSE SAND: BROKEN BED ROCK | 23,000 | 18,000 | 23,000 | 18,000 | 18,000 | * | * |
| CLASS 4 | CLAYPAN: MEDIUM DENSE SAND: SANDY GRAVEL | 20,000 | 14,000 | 20,000 | 14,000 | 14,000 | * | * |
| CLASS 5 | VERY STIFF CLAY: MEDIUM SAND | 16,000 | 10,000 | 16,000 | * | * | * | * |
| CLASS 6 | STIFF-VERY STIFF CLAY: MEDIUM FINE TO COARSE SAND | 12,000 | 6,000 | 12,000 | * | * | * | * |
| CLASS 7 | LOOSE FINE SAND | 10,000 | 6,000 | 10,000 | * | * | * | * |
| CLASS 8 | SWAMP AND MARSHES | * | * | * | * | 9,000 | * | * |

* NOT PRACTICAL TO INSTALL IN THIS CLASS SOIL.
NOTE: 3/4" ROD HAS AN ULTIMATE STRENGTH OF 23,000 LBS.


DJWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

DATE: MARCH, 1991

REVISIONS

ELECTRIC CITIES
OF GEORGIA

10.12



DETAIL ANCHOR GUY

E1


POWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

DATE: MARCH, 1991

REVISIONS

ELECTRIC CITIES
OF GEORGIA

10.01



TO BE USED ONLY WHEN VERTICAL
CLEARANCE UNDER GUY IS NECESSARY

SIDEWALK GUY

E-1-S


POWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

REVISIONS _____

ELECTRIC CITIES
OF GEORGIA

DATE: MARCH, 1991

10.02



NOTE:
CONNECT ALL STRANDS OF GUY WIRE
TO GROUND OR NEUTRAL.

DETAIL SPAN GUY


POWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

REVISIONS _____

ELECTRIC CITIES
OF GEORGIA

DATE: MARCH, 1991

10.06




NOTE:

1. USE WHERE SPAN GUY MAY CONTACT ENERGIZED CONDUCTOR OR EQUIPMENT IF SPAN GUY BECOMES LOOSE OR BROKEN.
2. FIBERGLASS LINK SHOULD BE INSTALLED BELOW ENERGIZED AREA, BUT ABOVE PEDESTRIAN REACH. (MIN. 10' ABOVE GROUND)
3. INSTALL #2-7 STRAND COPPER GROUND WIRE ABOVE SYSTEM NEUTRAL. CONNECT #2-7 COPPER TO STRAND TO SYSTEM NEUTRAL AND CONNECT #6 COPPER GROUND WIRE TO #2-7 STRAND COPPER WIRE.

GUY STRAIN ISOLATOR INSTALLATION

| | | |
|---|-----------------|-------------------------------|
| POWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA. | REVISIONS _____ | ELECTRIC CITIES
OF GEORGIA |
| DATE: MARCH, 1991 | _____ | 10.07 |




NOTE:

1. GROUND RESISTANCE (MEGGAR READING) SHOULD BE 25 OHMS OR LESS AT POLES WHICH SUPPORT EQUIPMENT REQUIRING LIGHTNING ARRESTERS.
2. EQUIPMENT POLES SHOULD HAVE A MINIMUM OF 3 RODS EITHER DRIVEN AT LOCATION NO. 1 OR ONE ROD IN THREE LOCATIONS.
3. ALL OTHER POLES SHOULD HAVE AT LEAST ONE GROUND ROD.

DIRECTION OF TRAFFIC →

STREET

ONLY ONE GROUND WIRE TO EXTEND DOWN POLE.



NOTE:

IF DRIVEWAY OR OTHER OBSTRUCTIONS INTERFERE WITH THE GROUND ROD LOCATION AS SHOWN, THE GROUND LEAD DOWN THE POLE MAY BE PLACED AT ALTERNATE LOCATION.

IN CASES WHERE TELEPHONE CABLE IS IN PLACE ON FIELD SIDE OF POLE, INSTALL GROUND ON ROAD SIDE QUADRANT AWAY FROM FLOW OF TRAFFIC.

METHOD OF INSTALLING GROUND RODS

M-2

VER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

REVISIONS _____

ELECTRIC CITIES
OF GEORGIA

DATE: MARCH, 1991

11.01


**DISTRIBUTION TRANSFORMERS
SIZING AND FUSING**

DISTRIBUTION TRANSFORMER FUSING

| FUSING
FACTOR | N
FUSE | K OR T
FUSE | CUTOUT
RATING |
|------------------|-----------|----------------|------------------|
| 1 | 1 | 1 | |
| 2 | 2 | 2 | |
| 3 | 3 | 3 | |
| 5 | 5 | - | |
| 8 | 8 | 6 | |
| 10 | 10 | 8 | |
| 15 | 15 | 10 | 50,100,200 |
| 20 | 20 | 12 | |
| 25 | 25 | 15 | |
| 30 | 30 | 20 | |
| 40 | 40 | 25 | |
| 50 | 45 | 30 | |
| 60 | 50 | 40 | |
| 75 | 75 | 50 | |
| 100 | 85 | 65 | |
| 125 | 95 | 80 | 100,200 |
| 150 | 100 | 100 | |
| 200 | 125 | - | |
| 240 | 150 | 140 | 200 |
| 320 | 200 | 200 | |

FUSING FACTOR OPTIONS

- 1.5 TIMES THE TRANSFORMER RATING WHERE MOTOR STARTING IS NEGLIGIBLE
- 2.0 TIMES THE TRANSFORMER RATING (STANDARD PRACTICE)
- 2.4 TIMES THE TRANSFORMER RATING(1 AMP PER KVA AT 2400 V)
- 3.0 TIMES THE TRANSFORMER RATING WHERE MOTOR STARTING IS SEVERE



| INITIAL LOADING | | | | |
|-----------------|-----------------|---------|-----------------|---------|
| KVA
SIZE | SUMMER PEAK KVA | | WINTER PEAK KVA | |
| | MINIMUM | MAXIMUM | MINIMUM | MAXIMUM |
| 5 | 0 | 6 | 0 | 7 |
| 10 | 6 | 12 | 7 | 15 |
| 15 | 12 | 18 | 15 | 22 |
| 25 | 18 | 30 | 22 | 37 |
| 37.5 | 30 | 45 | 37 | 56 |
| 50 | 45 | 60 | 56 | 75 |
| 75 | 60 | 90 | 75 | 110 |
| 100 | 90 | 120 | 110 | 145 |

| LOADING TO JUSTIFY CHANGE OUT | | |
|-------------------------------|-----------------|-----------------|
| KVA
SIZE | SUMMER PEAK KVA | WINTER PEAK KVA |
| 5 | 8 | 9 |
| 10 | 16 | 18 |
| 15 | 24 | 27 |
| 25 | 40 | 45 |
| 37.5 | 60 | 67 |
| 50 | 80 | 90 |
| 75 | 115 | 130 |
| 100 | 155 | 175 |

NOTE: IN THOSE CASES WHERE NO LOAD GROWTH IS EXPECTED, LOAD ON INITIAL INSTALLATION MAY BE INCREASED ABOVE THAT SHOWN FOR INITIAL LOADING.

DISTRIBUTION TRANSFORMER LOADING

| | | | |
|-------------------------|-----------------------|-----------------|---------------------------|
| DRAWN BY <u>E.C.B.</u> | DATE <u>FEB. 1964</u> | REVISIONS _____ | NUMBER
A-324-GO |
| TRACED BY <u>C.R.S.</u> | SCALE _____ | _____ | |
| APPROVED <u>E.C.B.</u> | <u>1-1-65</u> | _____ | |

ARRESTORS

Metal oxide varistor (MOV) arrestors are to be used for all new construction.

Arrestor leads should be as short as possible in order to maintain the lowest possible discharge voltage and highest possible protection level.

Arrestors are to be installed on the source side of cutouts protecting transformer, capacitor, cable risers and other appropriate distribution equipment. Underground cables shall be protected by riser pole or station class arrestors.

Arrestors are to be installed at all normally open and deadend points in order to reduce the possibility of flashover from surge reflection.

Arrestor grounds are to be 25 ohms or less and connected to the arrestor with #6 Cu or larger.

Why Should You Replace Old Station and Intermediate Class Arresters?

There are a number of reasons to begin a program to identify and replace old arresters in substation locations:

1. Better Equipment Protection

- A. There have been substantial reductions in the IR discharge voltages of arresters over the years. (See Figure 1). Installing new arresters can add substantially to the protection you give an old transformer.
- B. The metal oxide arresters eliminate front-of-wave sparkover. The equivalent discharge voltage provides 15 percent better protection.

2. More Durable Arresters — Greater Safety

- A. Arresters made prior to 1957 probably have little, if any, pressure relief capability. An arrester failure may be violent.

3. Reduced Chance of Failures Due to Contamination

- A. Gapped silicon carbide arresters may be prone to failure when surface leakage currents upset the grading and cause internal sparkover. Replacing these arresters should be a number one priority because they may have no pressure relief.

- B. Metal oxide arresters have high resistance to contamination problems.


4. Reduced Circuit Breaker Costs

- A. Switching surge voltages can be reduced by use of pre-insertion resistors in the circuit breaker design. However, properly located modern MOV arresters can absorb so much energy that the resistors can often be omitted.

If resistors in older breakers are damaged or require frequent maintenance, it may be more economical to install arresters of a modern MOV design.

-CHIO/BRASS-

Figure 1



13 & 23 KV

E-5.3.3




FIGURE 1.
VERTICAL CONSTRUCTION
ARRESTER INSTALLATION

NOTES:

1. ALL POST INSULATORS SHOWN ARE 35KV TIE TOP. USE CLAMP TOPS WHERE INDICATED BY ANGLE AND SIDE PULL LIMITATIONS SHOWN ON E-4. USE 45KV POST INSULATORS (CLAMP TYPE) ON 23KV CIRCUITS IN SALT CONTAMINATED AREAS.
2. PRIMARY TO NEUTRAL SEPARATION AT POLE DETERMINED BY MINIMUM MIDSPAN SEPARATION (DERM 4.4.1). IN NO CASE SHALL SEPARATION AT POLE BE LESS THAN 60" FOR WOOD POLES 40" FOR CONCRETE POLES.
3. "MINIMUM" DIMENSIONS MAY BE USED TO AVOID POLE CHANGEOUT OR EXCESSIVE GRADING TO A TALLER POLE.
4. SEE E-5.9 FOR VERTICAL DEADEND CONFIGURATION FIGURE 3.
5. POLYMER ARRESTERS TO BE USED WITH THIS FRAMING.
6. VERTICAL SPACING : 24" MINIMUM CONCRETE POLES
32" MINIMUM WOOD POLES

SUPERSEDES E-5.3 LAST REVISED ON 3-1-88

STANDARDS
OH & UG DISTRIBUTION SYSTEM
FLORIDA POWER & LIGHT COMPANY

| | | | | | | | | | |
|--|--|-------|--|---|--|--------------|--|--|--|
| FLORIDA POWER & LIGHT COMPANY | | | | | | | | | |
| REVISED NOTE #2 AND ADDED
NOTE #5 FOR VERTICAL
SEPARATION. | | H.O. | | DRA. J.M.
DRAWN: J.R. FILARDO
(DES) C.W.H. (ODS) J.S.B. | | NO SCALE | | APPROVED | |
| DATE | | ORIG. | | DES. ODS
CHECKED | | DATE: 1-1-80 | | R.K. CIELO
DIRECTOR, DISTRIBUTION ENGINEERING
AND SERVICE PLANNING | |


CAPACITORS

Capacitors installed in most locations shall be fused at a point to the left of the 10% probability case rupture curve.

Capacitors installed in locations where tank rupture and fluid leakage do not create a hazardous condition may be fused between the 10% and 50% probability case rupture curves.

Current limiting fuses shall be installed at any location where fusing results in a point located to the right of the 50% probability case rupture curve.

CURRENT IN RMS AMPERES*



GENERAL ELECTRIC

DIELEKTROL III™ FILM/FOIL CAPACITOR UNITS
10% PROBABILITY CASE RUPTURE


GES-9506

Safe Zone—Fuse clearings to the left of these curves are safe for most applications.
Usually no greater damage than slight swelling of the case will result.
Note—See GES-9507 for fuse clearings to the right of these curves.

* For times shorter than one cycle, use asymmetrical rms amperes.

CAPACITOR PRODUCTS DEPT., HUDSON FALLS, N. Y. 12839

CURRENT IN RMS AMPERES*



GENERAL ELECTRIC

DIELEKTROL III™ FILM/FOIL CAPACITOR UNITS 50% PROBABILITY CASE RUPTURE

GES-9507

Zone 1 - Fuse clearings to the left of these curves but above the 10% probability curves of GES-9506, are suitable for locations where case rupture and/or fluid leakage would present no hazard.

Zone 2 - Fuse clearings to the right of these curves are suitable for locations which have been chosen after careful consideration of possible consequences associated with violent rupture of case.

* For times shorter than one cycle, use asymmetrical rms amperes.

CAPACITOR PRODUCTS DEPT., HUDSON FALLS, N. Y. 12839

**NATIONAL ELECTRIC SAFETY CODE
CLEARANCE REQUIREMENTS**

| NATURE OF SURFACE UNDERNEATH WIRES, CONDUCTORS, OR CABLES | COMMUNICATION WIRE & CABLES, GUYS, MESSENGERS, NEUTRAL CONDUCTORS EFFECTIVELY GROUNDED. DUPLEX, TRIPLEX, & QUADRAPLEX SECONDARY

(IN FEET) | 0 TO 750 V. OPEN WIRE SECONDARY | OPEN SUPPLY LINE CONDUCTORS (IN FEET) | | VOLTAGES ARE PHASE TO GROUND. |
|---|--|---------------------------------|---------------------------------------|------------|-------------------------------|
| | | (IN FEET) | 750 V. -22KV | 22KV -50KV | |
| | | | | | |
| WHERE WRES CROSSES OVER | MINIMUM VERTICAL CLEARANCE | | | | |
| A: TRACK RAILS OF RAILROADS | 33 FEET MINIMUM ALL CLASSES | | | | |
| B: ROADS, STREETS, ALLEYS, NON-RESIDENTIAL DRIVEWAYS, PARKING LOTS, AND OTHER AREAS SUBJECT TO TRUCK TRAFFIC (8' IN HEIGHT) | 18 | 18 | 20 | 21 | |
| C: RESIDENTIAL DRIVEWAYS, COMMERCIAL AREAS NOT SUBJECT TO WORK TRUCK TRAFFIC (8' IN HEIGHT) | 12 | 15 | 20 | 21 | |
| D: OTHER LAND TRAVERSED BY VEHICLES SUCH AS CULTIVATED, GRAZING, FOREST, ORCHARD, ETC. | 18 | 18 | 20 | 21 | |
| E: SPACES OF WAYS ACCESSIBLE TO PEDESTRIANS ONLY. | 15★ | 15 | 15 | 16 | |
| F: WATER AREAS NOT SUITABLE FOR SAILBOATING OR WHERE SAILBOATING IS PROHIBITED. | 15 | 15 | 17 | 17 | |
| G: WATER AREAS SUITABLE FOR SAIL-BOATING INCLUDING LAKES, PONDS, RESERVOIRS, TIDAL WATERS, RIVERS, STREAMS, AND CANALS WITH AN UNOBSTRUCTED SURFACE AREA: | | | | | |
| (1) LESS THAN ACRES | 18 | 18 | 20 | 21 | |
| (2) 20 TO 200 ACRES | 26 | 26 | 28 | 29 | |
| (3) 200 TO 2000 ACRES | 32 | 32 | 34 | 35 | |
| (4) OVER 2000 ACRES | 38 | 38 | 40 | 41 | |
| *H: PUBLIC OR PRIVATE LAND AND WATER AREAS POSTED FOR RIGGING OR LAUCHING SAILBOATS. | | | | | |

* CLEARANCE ABOVE GROUND SHALL BE 5 FEET GREATER THAN IN "G" ABOVE, FOR THE TYPE OF WATER AREAS SERVED BY THE LAUNCHING SITE.

NOTE: FOR "E"

★ MAY BE REDUCED TO 12 FEET FOR QUADRAPLEX, TRIPLEX, & DUPLEX OPERATING AT 300 VOLTS TO GROUND OR LESS.

NOTE FOR "G" & "H":

(A:) FOR CONTROLLED IMPOUNDMENTS, THE SURFACE AREA AND CORRESPONDING SHALL BE BASED UPON THE DESIGN HIGH WATER LEVEL. FOR OTHER WATERS, THE SURFACE AREA SHALL BE THAT ENCLOSED BY ITS ANNUAL HIGH WATER MARK, AND CLEARANCE SHALL BE BASED ON THE NORMAL FLOOD LEVEL. THE CLEARANCE OVER RIVERS, STREAM, AND CANALS SHALL BE BASED UPON THE LARGEST SURFACE AREA OF ANY 1 MILE LONG SEGMENT WHICH INCLUDES THE CROSSING. THE CLEARANCE OVER A CANAL, RIVER, OR STREAM NORMALLY USED TO PROVIDE ACCESS FOR SAILBOATS TO A LARGER BODY OF WATER SHALL BE THE SAME AS THAT REQUIRED FOR THE LONGER BODY OF WATER.

(B:) WHERE THE U.S. ARMY CORPS OF ENGINEERS, OR THE STATE, OR A SURROGATE THEREOF HAS ISSUED A CROSSING PERMIT, CLEARANCES OF THAT PERMIT SHALL GOVERN.

FOR MORE INFORMATION OR DETAILS SEE RULE 232 AND TABLE 232-1 IN THE NATIONAL ELECTRICAL SAFETY CODE, CURRENT EDITION.

MINIMUM VERTICAL CLEARANCES OF WIRES, CONDUCTORS, AND CABLES ABOVE GROUND, RAILS, OR WATER.


POWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

REVISIONS _____


ELECTRIC CITIES
OF GEORGIA

DATE: MARCH, 1991

5.01



V - MINIMUM VERTICAL CLEARANCE MEASURED
EITHER DIAGONALLY OR VERTICAL



H - MINIMUM HORIZONTAL CLEARANCE

| CLEARANCE OF BUILDINGS | COMMUNICATION WIRES &
CABLES, GUY, MESSENGERS,
NEUTRAL CONDUCTORS,
EFFECTIVELY GROUNDED
DUPLEX, TRIPLEX, &
QUADRAPLEX SECONDARY
(IN FEET) | 0 TO 750 V.
OPEN WIRE
SECONDARY
(IN FEET) | OPEN SUPPLY
LINE
CONDUCTORS
(IN FEET) | | |
|--|---|--|--|---------------|--|
| | | | 750 V.
8.7KV | 8.7KV
22KV | |
| | | | VOLTAGES ARE PHASE TO GROUND. | | |
| HORIZONTAL | | | | | |
| TO WALLS AND PROJECTIONS | 4.5 | 5 | 7.5 | 7.5 | |
| TO UNGUARDED WINDOWS | 4.5 | 5 | 7.5 | 7.5 | |
| TO BALCONIES AND AREAS
ACCESSIBLE TO PEDESTRIANS | 4.5 | 5 | 7.5 | 7.5 | |
| VERTICAL | | | | | |
| ABOVE OR BELOW ROOFS
OR PROJECTIONS NOT
ACCESSIBLE TO PEDESTRIANS | 3 | 10.5 | 12.5 | 12.5 | |
| ABOVE OR BELOW BALCONIES
AND ROOFS ACCESSIBLE TO
PEDESTRIANS | 10.5 | 11.5 | 13.5 | 13.5 | |
| ABOVE ROOFS ACCESSIBLE TO
TRUCK TRAFFIC | 15.5 | 16.5 | 18.5 | 18.5 | |
| ABOVE ROOFS ACCESSIBLE TO
VEHICLES, BUT NOT SUBJECT
TO TRUCK TRAFFIC | 10.5 | 11.5 | 13.5 | 13.5 | |
| SIGNS, CHIMNEYS, RADIO AND
TELEVISION ANTENNAS, TANKS
AND OTHER INSTALLATIONS
NOT CLASSIFIED AS BUILDINGS
OR BRIDGES | | | | | |
| (a) HORIZONTAL | 3 | 5.5 | 7.5 | 7.5 | |
| (b) VERTICAL ABOVE OR BELOW | 3 | 6 | 8 | 8 | |

VERTICAL CLEARANCE

(a) CONDUCTOR TEMPERATURE OF 60 F., NO WIND, FINAL UNLOADED SAG IN THE WIRE, CONDUCTORS, OR CABLES.

(b) SPAN LENGTHS NOT GREATER THAN 250 FEET.

DIAGONAL CLEARANCE

THE HORIZONTAL CLEARANCE GOVERNS ABOVE THE ROOF LEVEL OR TOP OF AN INSTALLATION TO THE POINT WHERE THE DIAGONAL EQUALS THE VERTICAL CLEARANCE REQUIREMENT. SIMILARLY, THE HORIZONTAL CLEARANCE GOVERNS ABOVE OR BELOW PROJECTIONS FROM BUILDINGS, SIGNS, OR OTHER INSTALLATIONS TO THE POINT WHERE THE DIAGONAL EQUALS THE VERTICAL CLEARANCE REQUIREMENT.

FOR ADDITIONAL INFORMATION AND DETAILS SEE RULE 234 AND 234-1 IN THE NATIONAL ELECTRICAL SAFETY CODE, CURRENT EDITION.

CLEARANCES OF WIRES, CONDUCTORS AND CABLES PASSING BY BUT NOT ATTACHED TO BUILDINGS AND OTHER INSTALLATIONS EXCEPT BRIDGES.


OWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

REVISIONS

ELECTRIC CITIES
OF GEORGIA

DATE: MARCH, 1991

5.02



1. IF SPAN LENGTH EXCEEDS 250', CONDUCTOR CLEARANCE IS TO BE INCREASED 0.3 FEET FOR EACH 10 FEET SPAN LENGTH EXCEEDS 250 FEET.
2. CROSSINGS SHOULD BE MADE ON A COMMON SUPPORT STRUCTURE WHERE PRACTICAL. COOPERATION BETWEEN THE PARTIES CONCERNED SHALL PREVAIL PROPER CLEARANCES.
3. EXCEPTIONS TO 12' HORIZONTAL SIDE CLEARANCE
 - (a) A CLEARANCE OF NOT LESS THAN 7 FEET MAY BE ALLOWED WHERE NECESSARY THE SUPPORTING STRUCTURE IS NOT THE CONTROLLING OBSTRUCTION, PROVIDED SUFFICIENT SPACE FOR A DRIVEWAY IS LEFT WHERE CARS ARE LOADED.
 - (b) WHERE NECESSARY TO PROVIDE SAFE OPERATING CONDITIONS WHICH REQUIRE AN UNINTERRUPTED VIEW OF SIGNALS, SIGNS, ETC. ALONG TRACKS THE PARTIES CONCERNED SHALL COOPERATE IN LOCATING STRUCTURES TO PROVIDE THE NECESSARY CLEARANCE.
 - (c) AT INDUSTRIAL SIDINGS, A CLEARANCE OF NOT LESS THAN 7 FEET SHALL BE PERMITTED, PROVIDED SUFFICIENT SPACE IS LEFT WHERE CARS CAN BE LOADED OR UNLOADED.

RAILROAD CROSSING CONSTRUCTION CLEARANCES

POWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

REVISIONS _____


ELECTRIC CITIES
OF GEORGIA

DATE: MARCH, 1991

5.03

***COMMUNICATION/SIGNAL TYPE ATTACHMENT**

TELEPHONE CABLE
C.A.T.V. CABLE
ALARM CABLE (FIRE, POLICE, WATER
TOWER LEVEL, ETC.)
TRAFFIC SIGNAL CONTROL CABLE
TELEGRAPH CABLE
PUBLIC OR PRIVATE COMMUNICATION
CABLE




NOTE:

WHEN C.A.T.V. AND TELEPHONE ARE ATTACHED TO POLE C.A.T.V.'S PREFERRED POSITION IS ABOVE TELEPHONE (12" MIN.). IF OTHER COMMUNICATION/SIGNAL TYPE CABLES ARE ATTACHED TO POLE WITH C.A.T.V. AND/OR TELEPHONE, THEIR POSITION SHALL BE MUTUALLY AGREED UPON. 12" MIN. SPACING SHOULD BE MAINTAINED BETWEEN CABLES. C.A.T.V. AND TELEPHONE DROPS CAN BE LESS THAN 12" FROM OTHER CABLES. DROPS SHALL BE 40" BELOW POWER NEUTRAL OR SECONDARY AT POLE.

POWER NEUTRAL OR
SECONDARY CONDUCTOR OF
NOT MORE THAN 750 VOLTS
TO GROUND.

ALL CABLES SHALL BE ON SAME
SIDE OF POLE.

MESSANGER STRAND SHALL BE
BONDED TO POLE GROUND, IF
PRESENT.



**MULTIPLE COMMUNICATION/
SIGNAL TYPE ATTACHMENT**

POWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

REVISIONS _____


ELECTRIC CITIES
OF GEORGIA

DATE: MARCH, 1991

5.04

***COMMUNICATION/SIGNAL TYPE ATTACHMENT**

TELEPHONE CABLE
C.A.T.V. CABLE
ALARM CABLE (FIRE, POLICE, WATER
TOWER LEVEL, ETC.)
TRAFFIC SIGNAL CONTROL CABLE
TELEGRAPH CABLE
PUBLIC OR PRIVATE COMMUNICATION
CABLE



COMMUNICATION/SIGNAL TYPE ATTACHMENT CLEARANCE FROM OUTDOOR LIGHT

POWER ENGINEERING ASSOCIATES, INC.
MARIETTA, GA.

REVISIONS _____

ELECTRIC CITIES
OF GEORGIA

DATE: MARCH, 1991

5.05